# IN THE CIRCUIT COURT OF THE ELEVENTH JUDICIAL CIRCUIT IN AND FOR MIAMI-DADE COUNTY, FLORIDA

CASE NO: <u>2021-015089-CA-01</u> SECTION: <u>CA43</u> JUDGE: <u>Michael Hanzman</u>

In re:

Champlain Towers South Collapse Litigation

### RECEIVER'S EMERGENCY MOTION FOR ENTRY OF ORDER AUTHORIZING RECEIVER TO SIGN PERMIT APPLICATION REQUESTED BY MIAMI-DADE COUNTY AUTHORIZING BOFAM CONSTRUCTION COMPANY, INC. TO UNDERTAKE EMERGENCY WORK TO BRACE THE <u>WEST RETAINMENT WALL AT THE PROPERTY</u>

Michael I. Goldberg (the "Receiver"), pursuant to Rule 4 of the Complex Business Litigation Rules, seeks entry, on an emergency basis, of an order authorizing the Receiver to sign a permit application requested by the Miami-Dade County Department of Regulatory and Economic Resources (the "County") authorizing Bofam Construction Company, Inc. ("Bofam") to undertake emergency work to brace the west retainment wall at the former site of the Champlain Tower South Condominium located at 8777 Collins Avenue, Surfside, Florida 33154 (the "Property"), so that additional lanes of Collins Avenue adjacent to the west side of the Property can safely be opened.<sup>1</sup> In support of this Motion, the Receiver states as follows:<sup>2</sup>

<sup>&</sup>lt;sup>1</sup> The relief sought in this Motion is directly related to the relief sought in a prior motion filed by the Receiver (Filing # 132119264) on August 5, 2021 seeking entry of an order authorizing him to sign a permit application requested by the County authorizing Bofam to undertake emergency work to brace all of the retainment walls at the former site of the Property (the "**Initial Motion**"). The instant Motion also concerns the bracing of retainment walls at the former site of the Property, but is focused solely on bracing the west retaining wall so that additional lanes of Collins Avenue adjacent to the west side of the Property can safely be opened.

<sup>&</sup>lt;sup>2</sup> The County has also requested the Receiver to execute a permit application for "dewatering" work on the Property. It is the Receiver's understanding that certain pipes will be placed on top of the foundation that will continually remove water from the Property. The Receiver was hoping to file the motion to authorize him to execute the "dewatering" permit application simultaneously herewith, however, the County has not yet received approval from DOT to pump the water into DOT controlled storm drains which is part of the plan. It is expected that a motion to authorize the Receiver to execute the dewatering permit application will be filed in the near future.

1. At a hearing conducted on July 2, 2021 the Court ordered the appointment of Michael I. Goldberg as receiver for the Champlain Tower South Condominium Association.

2. This receivership is the result of multiple lawsuits that were filed after the tragic collapse of the Champlain Tower Condominium previously built on the Property.

3. The County maintains control over the Property as the County and NIST investigate the circumstances leading up to the collapse of the Champlain Tower South Condominium. The County has notified the Receiver that it believes that the west retaining wall at the Property needs to be buttressed so that additional lanes of Collins Avenue adjacent to the west side of the Property can safely be opened.

4. To that end, the County has hired Bofam to perform the necessary work to buttress the west retaining wall. The work Bofam intends to perform is more fully set forth in the engineering plans attached to this Motion as **Composite Exhibit "A"**.

5. In connection with the work to be performed, Bofam commissioned and obtained a safety report (the "Safety Report") from Calc Engineering, LLC ("Calc"). A copy of the Safety Report is attached hereto as **Exhibit "B"**. <sup>3</sup> As depicted in pictures on page 25 and 26 and discussed on page 7 of the Safety Report, rebar is sticking out of the western retaining wall in a haphazard manner and there is also some loose concrete hanging from the west retaining wall. Pursuant to the Safety Report, in order for Bofam to safely be able to undertake the work necessary to buttress the west retaining wall, Calc is recommending that the rebar on the west retaining wall

<sup>&</sup>lt;sup>3</sup> The Safety Report was obtained by the County in early August in connection with the original intended scope of work which was to buttress all the retaining walls and was contemplated in the permit application which was the subject of the Initial Motion. The current permit application the County has requested the Receiver to execute which is the subject of the instant motion seeks only to buttress the western retaining wall adjacent to Collins Avenue. Accordingly, the scope of the Safety Report is much broader than the requirement to make the Property safe for Bofam to buttress the western retaining wall.

be cut and that the loose concrete on the west retaining wall be removed prior to Bofam undertaking work to buttress the west retaining wall.

6. The Receiver is unsure as to whether or not the rebar and loose concrete that the County seeks permission to remove have evidentiary value.<sup>4</sup> The Receiver requested the County to ask Bofam if the work could be performed without cutting or in any way altering the rebar or loose concrete and the County has informed the Receiver that it is not possible.

7. The County has assured the Receiver that the work to be undertaken is necessary for life-safety reasons and will be undertaken in a manner best designed to preserve the evidence in accordance with this Court's prior orders. The Receiver is not an engineering expert and is relying on the County and its experts that the work to be undertaken is necessary and will preserve the evidentiary value of the Property as best as possible under the exigent circumstances.

8. The Receiver is technically the "owner" of the Property even though the Property is currently under the County's control. Accordingly, the County has requested the Receiver to execute the Permit Application filed by Bofam. A true and correct copy of the Permit Application is attached hereto as **Exhibit "C"**. The Permit Application identifies the Applicant, provides the Applicant's Contractor and Qualifier Numbers and a \$362,685 estimate for the emergency shoring work to be performed. Bofam seeks issuance of a new permit authorizing it to perform emergency shoring work in respect of the Property.

9. The Receiver has informed the County that he will not execute the permit application unless and until he receives Court authorization to do so, and only after notice and a

<sup>&</sup>lt;sup>4</sup> The County has represented to the Receiver that the only rebar or cement that will be removed or otherwise altered is the rebar and loose concrete associated with the western retaining wall of the Property and rebar and loose cement approximately 20 feet inward on the side walls (north and south) adjoining the west wall.

hearing in which all parties in interest have an opportunity to consider the Motion and express their position to the Court with respect to the intended work and its potential impact on the Property.

10. The Receiver has conferred with lead counsel for the Plaintiffs who, in turn, has conferred with his group, and Plaintiffs have no objection to the relief requested in this Motion.

11. The Receiver and the County are well aware that some parties in interest may strenuously object to the work intended to be done by Bofam—especially the cutting of rebar and the removal of loose cement along the west retaining wall and the small portion of the adjoining walls prior to them having a chance to view the west retaining wall in its current state. To that end, the Receiver and the County have discussed the possibility of granting parties in interest the opportunity, with the Court's authorization, to enter the Property prior to Bofam commencing work to view and/or film the west retaining wall in its current state. The Receiver and the County are understandably concerned that the current state of the exposed rebar and lose cement is extremely dangerous and people may get hurt if granted access prior to Bofam completing its work.<sup>5</sup> Notwithstanding, the County agrees to permit parties in interest who are pre-approved by the Court to access the Property for the limited purpose of viewing and/or filming the west retaining wall prior to Bofam commencing work if: (i) the Court's order permitting access to such persons makes it clear that neither the County nor the Receiver shall have any liability whatsoever in the event a person is injured while on the Property; (ii) each person who enters the Property executes a release and hold harmless agreement prior to entering the Property releasing the Receiver and County from any and all claims that may arise by virtue of them entering the Property; (iii) the party in interest who requests access to the Property provides the Receiver and County with an insurance policy in the amount of \$2 million naming both the County and the

<sup>&</sup>lt;sup>5</sup> In fact, it is the Receiver's understanding that certain areas of the Property are considered so dangerous that even NIST was not able to safely access them.

Receiver as additional insureds under such policy; and (iv) the party in interest agrees to be bound by the Access Protocol (once finalized)<sup>6</sup> with respect to it or its agents entering the Property; and (v) each person who enters the Property shall be required to wear a N95 or equivalent mask, steel toe construction boots, a helmet and a reflective vest.<sup>7</sup>

**WHEREFORE**, the Receiver respectfully requests that the Court enter an Order authorizing him to approve or sign-off on the Permit Application, to the extent necessary, and grant such other, further and related relief as may be appropriate under the circumstances.

Dated: August 31, 2021

Respectfully submitted,

BERGER SINGERMAN, LLP Counsel for the Receiver 1450 Brickell Ave., Ste. 1900 Miami, Florida 33131 Telephone: (305) 755-9500 Fax: (305) 714-4340

By: s/ Paul Steven Singerman

Paul Steven Singerman Florida Bar No. 378860 Jordi Guso Florida Bar No. 863580 Paul A. Avron Florida Bar No. 50814 <u>DRT@bergersingerman.com</u> <u>Singerman@bergersingerman.com</u> <u>Jguso@bergersingerman.com</u> <u>MDiaz@bergersingerman.com</u> <u>Fsellers@bergersingerman.com</u>

<sup>&</sup>lt;sup>6</sup> To the extent there is a conflict between the Access Protocol and the Order emanating out of this Motion, the terms of the Order shall take priority with respect to the access being granted to view and film the west retaining wall.

<sup>&</sup>lt;sup>7</sup> The County has graciously agreed to provide a dozen helmets and reflective vests. To the extent more than a dozen people request permission to enter the Property, the Receiver shall coordinate access to the property is separate groups of 12 or less.

### **CERTIFICATE OF SERVICE**

**I HEREBY CERTIFY** that on August 31, 2021, a copy of the foregoing was electronically filed with the Clerk of Court by using the Florida Courts E-Filing Portal, which served a copy of same to all counsel of record through the Florida Court's E-Filing Portal. I further certify that a true and correct copy of the foregoing was served by electronic transmission and first class, U.S. Mail on August 31, 2021, upon all parties on the attached Service List.

By: <u>s/ Paul Steven Singerman</u> Paul Steven Singerman

### SERVICE LIST

Austin Akinrin, President Bofam Construction Co., Inc. 1600 NW 3<sup>rd</sup> Avenue Miami, FL 33136 austin@bofaminc.com

# **COMPOSITE EXHIBIT "A"**

CODES:	-waining	4. DO NOT NAL DEAN REARING ENDS TO LEDGER.			
1 NORM BRONG COR, PE 200, TH CITER.	BERDUS MULTER OF BEATH ON RESULT FROM YOUR FALLINE TO FAMELINE YOURSELF AND COMPLY WITH ALL	5 PROJECT AND WANTER ADDUCT SUPPORT TO PROFERLY OSTIMUSE SHORED LOADS WERE SUPPORTED			
<ol> <li>addicen robot and hardle utologichis functions, below</li> </ol>	APPLICABLE SAFETY RELATIONS OF PEDDIAL, STATE AND LOCAL REDUCTIONS, UNDERSTAND THERE SAFETY UNDERSTATS REPORT DESIGNATIONS, ON DEMANDING BAS	A) MATCHINY BALL - MILLE BARY MATCHINY (MIT) MARK ALED ARE UNDER MARK MARK AND AT	GENERAL NOTES:	DESIGN CRITERIAL:	
(14 & 74)	geore.	NEXESSARI, AL LENGTH OF BUT AND A CARD AND A CARD. OF	<ol> <li>CONTRACTOR SHALL VERITY ALL CARDIDALS AND CONCEPTING IN THE FIGLD FROM TO START OF ADDR. AND MOREY EXCEPTING ANY DECRETANCY IN THE CANADIDA. AND</li> </ol>	1. BASEMENT SHEET PELINE BALL MILE TO CARRY LOADS 1945N TEMPORARY BRADNE HESTORES ORIGINAL WALL TOP LATERAL SUPPORT CONCIDENT. ANY LODGE CONCIDENT	
<ul> <li>and second conclusion of the second se</li></ul>	A GENERAL	INTELED FOR RECOMMENDATION OF SUPPLEY OR JOB ADDITIONATION OF SUPPLEY OR	CREAM HE APPROVE, REPORT PROCEEDING WITH HOW.	COVER SHALL BE REMOVED AND BRACING FOP PLATE SHALL BE ATTACHED ERRECTLY TO SHEET FILLING.	
<ol> <li>Address concern scheme, an access, and access of concern schemes, an access.</li> </ol>	I USE SHORNO CONTINUES RECOMPLETE SHE HERBID	C) FORMATION = SHORED SEARS SHOLD BE LESING FOR THE ADDITIONAL LOADS MPOSED BY THE	MORESHARTS TO COMPLEX ALL HOW SHOWN ON THE DRAWNOS AND SPECIFIC HEREN.	2. BASED ON EXERTING STRUCTURES, DRAWINGS BASEMENT WALL CONSTRUCTION, OUR SITE VISITS AND OUR ENDANCEMENT AUGUSTATION BASEMENT WALL HE.	
<ol> <li>address solely of out benefits tensor stars since ray automation of the startings' and the</li> </ol>	4. SPAX, SPACING AND TITES OF SECRING MEMORYS B. THES, SUES, HEORITS AND SPACING OF VERTICAL	<ol> <li>STRUCTURAL STEEL PRINCHORY - THE ABLETY OF ME STEEL TO SUPPORT ALL LONDING MOULD BE</li> </ol>	3. DO NOT SCALE DRAWNOLL DISCUSSIONS CONTRACTOR THAT HE STREET AT THE	ADEQUATE FOR WARDENBORG THE TOP OF WALL LOADS TO BRACES STOLE HE BRACES AND SPACED AT SUCH CLOSED OPTIMUS THAT WILL RECEIVEE THE CONTINUES SUPPORT PROVIDED BY THE COMPLETE BIRST RECEIVER THE SLAD.	
<ol> <li>address without of USEs contraction will puts the genesi.</li> </ol>	PROFESSION PROFESSION CALL MARK OF	DHENED AND APPROVED BY THE REPORTING PROJECT ARCHITECT/ENCINEER	CONTRACTOR BEFORE COMMENCES OF WORK AND DURING CONSTRUCTION SHALL BE COORDINATED WITHIN 24 HOURS IN ADVANCE (FROM TO INSPECTION.	1. EXETING FIRST ELEVATED CONCRETE (LAR'S REMAINING STEEL REPORTMENT HANGING	
GENERAL NOTES	CREMENCI BELOW SHEE PLATES FOR SHE DISTRIBUTION OF LET LISHES TO CONCRETE SLARS OF OFQUIND, EXISTING	E) STEEL NAMOUSS + 3E SUPE THE DEARING ENCS FALLY ENGALE ON THE NAMOENS THE NAMOENS SHALL HE OFSIDED TO CONFORM TO THE BEARING.	3. DO NOT SUBSTILLE WARRANG, EXAMPLETS OF METHODS OF CONSTRUCTION UNLESS SUCH SUBSTILLENS OF DRIVES HAVE NEW ADDRESS IN BRITISH OF THE EXAMPLE.	AT TOP OF EXERTING BALEMENT WALL SHALL BE AVOIDED AND/OR REMOVED TO GIVE WAY TO BRACING SYSTEM TOP ATTRCHMENTS.	
THESE DRAWING SHOW THE APPLICATION OF SHOPING PRODUCTS TO THIS SPECIFIC PROJECT, BULDING OR CTRUSTERIES AND ANY REFER ON DESIDENCE CONTINUES.	HOR TO DECIDE AN HONOLD, COMPLET HOR TO DECIDE OF SHORE TO HELENT SETTEMENT, CONSERVATION WITH OVEN TO	BID and seed, save a halfo should be safely support the second cours merces.	6. THE CONTRACTOR IS SOLLY RESPONDED FOR MEANS AND METHODS OF	4. ROAD BARRERS MIL HE INSTALLED (MOT), BY OTHERS, AT A DESTANCE SHOW ON OUR PLANS FOR REFERENCE. THAT WILL PREVENT ROADWAY USERS FROM FALLING INTO	
PROJECT CON-EXAULTION DRAMINGS SUPPLIED TO RC OROUP LLC BY THE CUSTOMER THESE DRAMINGS DO NOT SHOW ALL	POTENTIAL ADVERTIGATION AS BALENCE THEOLOGICAT THE POLIN CYCLE SUCH AS BALENCES, PREEZING AND	WHE THRE CHECK WITH WARLFACTURER OF HANGERS FOR SPECIFIC APPLICATION. (FOLLOW	1. THESE DWOST ARE NOT VIEW METSOUT THE SIGNATURE AND RATED SEAL OF THE	S. WE WELL USE A LINE LOAD VEHICILAR TRAFFIC SURFACE HORZONTAL SURDHARSED	RESERVED FOR GITY STAMP AREA
SPECIFIC ON-SITE LESION EXTERNS INVESTIGATION OF THE LESION DETAILS INVESTIGATION AND THE THE PERFONSION OF THE CUSTOMER.	ENGINEER TO DETERMINE THE PROPER SUE FOUNDATION REQUIRED FOR EXISTING DROUND CONDITIONS.	RANGER MANUFACTURE'S RECOMPORTONS)	STRUCTURE EXCREMENT AND FOR THE ADDRESS WITH IN THE INCOMENT	LOAD, AGAINST EXESTING BACK OF BACENET BALL BACED ON ASHTD 3.11.8.1. FORMULA 3.31.8.4-1 AND TABLE 3.11.8.4-2.	MEVERONS
1. ALL DEDUDOS AND DETALS SHOW ON THIS LAND."	3.50 KOT WHE UNKNOWNED DWHEES OF SUBSTITUTION OF ECONOMIC ACCENT CONTRACT YOR DECEMIN	16 10.46 Yest.	N POP ML	<ol> <li>BRACHS AND RE-SHORING WELL RE DESIGNED FOR ALL APPLICABLE CODE LOADS FOR THE PRESENT CONDITION OF MENTIONED. INSTALLED IN THIS SITE, ME WELL LITE CODE</li> </ol>	
BPOR PRODEING WIN ANY BOR.	CONFAVY SUPPLIER PROF TO WHAT CONFIDENT ACCESSION OF ADD STRE CONDITIONS.	1. THERE IS SOUND POLYDOR WHERE WERE WERE WERE	EXTEND CONCRETE STRUCTURE, DAMENTS UNDER THE POOL (ECK AS SHORN ON SHERE DEVENDED, BREED IN OUR DAMEDING ACCOUNTS AND DEPENDENCE, THIS	THE MAT THE EDAMENT THE PERMANES STUCTURE ABOVE DUE TO THE LENGTH OF THE MAT THIS EDAMENT WELL BE STRUCTURES.	
<ol> <li>by approximate second of some acceleration read men second terms from the extension was made to be admitted by to PED conditions. Instructs, but</li> </ol>	A ACCESS MULT BE PROVIDED TO ALL FORMAL DECK LEASES IF IT IS NOT AURLAUE FROM THE STRUCTURE.	<ol> <li>ALL BATE PLATES AND SOTEX JACKS ARE IN PRIV CONTACT WITH POLYGATION.</li> </ol>	INVESTIGATION AND AND AND AND AND AND AND AND AND AN	<ol> <li>COLTING CONCRETE STRUCTURAL BASEMENT SLAB MEL DE USED TO SUPPORT TEMPORARY DIRADNE SYSTEM HORIZONTAL AND VENTICAL REACTON. DEARDATED</li> </ol>	
scence scene and pripers for his last, it is the second in the second se	ACCESS LADGERS OR STAR TOMOS WUST BE PROVIDED. ACCESS LADGERS WUST EXTEND AT MEAST THREE (3) REST ADDRE TOMOSTIK	5. EXEMPTIONFORMUT ONCLUDING EXTERIOR INFACTION ADREED WITH THE SHORED LATOLITY AS TO TIPE, SPAIN,	SHOW ON THESE DRAWNOS. ALL & ROUTINE WATTER, IN OPDER TO AVOID FOLDINE, WELL-DEPETHNENCES, NOTIFIED IN THE DRAWNOS INFOLD BE CONSTRUCT, DRECTLY OF	R. AS FOR DISTRUCTURAL PLANS, ENSING CONDICTLE STRUCTURAL SLAR IS 9"	¥9
3. SUTARE BUS WIST IS PROVIDED TO PROPERT DISTRIBUTE THE MYOSED SHOPPING LOADS OVER THE	(BARNAG)	NUMBER, LOCATON AND SEE	HORELTLY, AS A GUMMANTER FOR PORTIONS OF THE INVESTIGATION OF COMPACE BY HEREIN RC ORGUP, LLC VIEW, OFERVATOL. TO SHE SETT OF WY KNOMEDGE AND ARUTY, SHE STATEMENT REPRESENTS AN ACCUMUTE APPRACEAL OF SHE PRESENT	THERE THIS VALUE IS CONSISTANT WITH THE AVERAGE VALUE MEASURED ON THE FIELD HAVED ON OUR WISHAL FIELD DISEDIVATIONS. THIS STRUCTURAL SLAW AVERAGES TO BE IN COST OFFICIENT AND A DISEDIVATIONS. THIS STRUCTURAL SLAW AVERAGES TO BE	바이프 말 것
GROUND OR SUPPORTING FOUNDATION TO ADDURE ACEDUATE STAINUTY FOR ALL SWORAD LEDS. USE COMPOSITE STAINUTY FOR ALL SWORAD LEDS. USE	FALL AREST EDUPAENT ATTACHED TO SECONG RELINCT PREVENT SERIOUS MULRY OR DEATH IF FALL OCCUPS.	AY40	CONDITION OF THE ABOVE WENTIONED FORTION OF THE STRUCTURE BASED UPON CAREFUL CHARACTER OF DESCRICT CONDITIONS, TO THE EXTENT REACONABLY	COLLAPSING	2107 C B
DN-RCT BY BOOD NALS OF BOUNLY SPACED TO COME OF CONTINUOUS &" BEADS EQUINALY SPACED TO COMER	S FASTER ALL BRACES SECURES.	<ol> <li>ALL PRAMES ARE PLUME AND BRACED TO FOMP TOMENS AND/OF ALL POSTS ARE PLUME AND BRACED AS MEDLARD BY UKER INSTRUCTIONS.</li> </ol>	HOLE VENTONED STRUCTURAL CNORETE DAVAGE	9. NO STADUART WATCH AT EXISTING CONCRETE STRUCTURAL BASEMENT SLAB, WATCH REMOVAL BY OTHERS.	¥36 3 6
TOUTING THE LANDER USED BD REACTING NALLS	CONCERNING LONGING AND ALL CLARPS, DOCES, PHS AND ALL CONCERNING COMPONENTS AND RE A CLOSED ON DECACED POSITION.	4. ALL FORMONY FOLLOWS FORMING LANDLE AND		10. MARKAN BRACHS STACKS WEL BE CAUGULTED AND REDMI ON PLANE.	
A ALL STRUCTUL LEDGED OF CHER MEMORY RESTOR	2 week certain text as each rights and those	1. ALL CLARPS, SCHERE, PNS AND CIMER PACIFICATION		( I. FREIDER HONORANY DEMANDER INF-LANDAURALE)	Apres 1
SHORED THE REAL PROPERTY OF AN	PERMIT MATCHAL	Declared Lobins of ACT IN ADACTION BENCO HT			A PAR B
5. AL SETTING BLEVISIONS, ALLOW FOR COMPRESSION OF LUNDER	SUPE SUPER PERFORMENCE PERFORMENCE OF THE	<ul> <li>turns, sectorizes</li> </ul>			ž.
<ol> <li>THE SHOREN EQUIPMENT OPICIED ON THIS AND THE ATTACHED DRAMINUS MUST BE EXECTED SO AS TO</li> </ol>	IN ANOLE ECCENTRIC LOADS ON U-READS AND TOP PLACES BY OENTENING STRINGERS ON THESE MEMORYS.	1. IN HURREARE SEASON (FROM JULE 1 THRU 30 NOVEMENDI E A STORY HIT THE AREA OF MORE	DESIGN LOADS:	DRAWINGS INDEX	л. •
SUPERANT AND TO ALL FEEDWAL STATE AND LOCAL REDUKTIONS	10 AVOD SHOK OF MART LOADS FOR WHOH THE DROPING WAS NOT DESIGNED.	IE-KOVECTORS IS REQUEE AT CONTRACTOR EXPENSES	1. MRG LOHOL BHODINY MALE = 48.30PW	99-00 (ENEXA, NOTES	- 'U' H
2. ML STEL HEAN LESCENS OF STRINGERS WIST HE	<ol> <li>SE CONFLETED SHOWS SETUP SHALL HAVE SE SPECIFIED INHONG TO GHE IT LATENAL STABUTE</li> </ol>	DO NOT POSITION WORKERS (MLOW FORWARK WHILL CONCRETE IS BEING PLACED)	2. BROWFEL SOL, UNITING ROMONIC TRANSLAM DISTRIBUTION ON BACK SUMPACE OF THE DESEMPT RELL SATURATED SOL PRESSUME AT TOP IS 0.0MJF AND A BASE OF	SHI-1 FLOOR PLAN, NOTES AND DETALS.	T Stars
PER LI-HEAD ON ALTERNATE SOLES (SEE CETAL "A" ON THE LI-HEAD ON ALTERNATE SOLES (SEE CETAL "A" ON	12. HE EXECTION OF SHORED THRUDO IN CONTENTS	R REACHAL	3. STREET LARE LOAD TRUCK SUPCOMPLE FOR BASEMENT WALLS PARALLEL TO HEMBAY	1944.2 SECTORS	B 193
STREADERS MUST HE SECURES TO U-READS BY THE (1) RUMPLIN REAR QUART	PORSON	LOADS SHORNS ESJENDED SHALL NOT BE RELEASED OF REMOVED. NOLLONG CROSS BRACES, UND, THE APPROVAL	TOULNE AND THATTE CONTROL IN THE ANDITO JULE TOMALE JULE AND THEM AND THEM AND A DISCHART OUTBOUTED HORIZONTHE SUPERIE LOAD & SUPER		
8. AT THE THE ME GEORE OF STRUCT IS PLACE IN THE UNHERS, IT MUST BE IMPERATELY SECURE TO THE	8 Date: Scotting	OF A QUALTED ENDEET AND BEEN RECEVED THEREAST. RELEASES OF STRETTING OF FORMS CAN EAVER FALLING. A QUALTED ENDEEP WILT DECKED WERE AND RUN			15 100
U-HEAD WOOD LEDGERS OF STRENGERS ARE NAMED DIRECTLY TO THE U-HEAD (THEVEDUL NOTE FOR SECURING	OWT HEARHED COMPONENTS.	streaming in to record a wanted charton, satisfies a determine range for the charton as the stream wanter of the consult as allocit for			T ON R
5. ALL LONGE PENNES OF A TONER MUST BE PUNK AND	HEARTS AS SHOWN ON THE SHOREG LARGUT	170HILL			99
LDB, BEFORE DECTING THE REMAINDER OF THE TORES.	3. SHOREG LEAD WITT BE CARRED ON ALL LEDS	DETINITION RESIDENCE MEANS THE CONSTRUCTION OPERATION IN MICH SHOPPIC EQUIPMENT IS PLACED, AS			ő
CONTRACTOR AND SHOULD BE THOROUGHLY CHECKED BY THE ANOMIECT/DUCAMED TO DETERMINE THAT IT IS	EXECTION PROCEEDS, AND ONE IN PLANE AND LEVEL OF SHORING TOMERS JUST PROF TO POURING.	THE ORDERAL FORME AND SHORES AND REVOLUTE, IN ORDER TO SUPPORT PARTIALLY DURED CONCRETE AND CONTRACTORS USED.	NOTE:		
TO SUPPORT THE AREAS THAT ARE HENG RESPONDED.	5. (0 x07 FORCE MALES ON FRANKS TO FT LEVEL THE THOMPS TOMETS UNTEL PROPER ITT CAN BE WARE	· HEROPHE IS ONE OF THE WOLT CHICKL OPERATIONS	POR DEPENDENCE INC. CONTROLD		
<ol> <li>TOMON LES LONDING SHELLES HE AS UNERDING? OFTEN/NED AS POTUNEX, MEMOR LOAD ONLY ONE USE OF A FEMALE OF ONE DEVICE A VIOLET.</li> </ol>	EXEX.	MUST BE DESIDED AND PLANED IN ADVANCE BY A SURFED STRUCTURE, ENDEDT AND APPROVED BY THE	CONFIGURATION, REFER TO	STOL OF THE STOLEN	2
12 AL DIAMOS BAT NODPORATE HORIZONTAL SHORED	SUPPORT BRACES TO MAKE A HOLD, SOLD UNIT CONSULT YOUR SECRET COMPANY REPRESENTATIVE FOR	PROJECT AROUND UNDER THE ADVISED BALLED	MANUFACTURER SPECIFICATION	Salt Change Contraction	8
INCOMENT THAN SHOTHON COMPANY'S MUST BE INCOMENT ACCORDING TO THE MINUTING TURBY'S DECISION INCOMENTS MEDIAL FOR SHOT OF ST	RECOMPERATIONS), DECEMPE WAST ALREYS HE SECURE WASN THE RECORT OF THE SHORE TOMONY ENCOUNT FOR	HE ALLINED TO THE SHE REMARKED SELECTION IN THE REMARKED STATES	1257	St No EAUE	1
FOR ALLISTRATINE PURPOSES ONLY AND SHOULD BE DECRED BY THE WANUFACTURES AND/OR SUPPLIES FOR	T DENDE ONTON & EXECTING ON DEMANTELING FIRE	A REPORT SHAL IF MADING DEDED IN		En	) <u>6</u>
USALDARANCE WERE THERE SPECIFICATIONS. 13. WHEN TOMERS AND GRADONALLY BRACED TO DRACE OF	EINCRU DEDRU TORPS TO PREMIT DAVIS. 8 00 NUT (LAR CROSS DRACES	THE ARCHITECT/ENGINEER TO SETENANE THAT IT IS PROPERLY PLACED AND THAT IT HAS THE ALLOHABLE		STATE OF	
SOME OTHER POINT, BY GUIRNE OF OTHER MEANS, THE MERTICAL COMPONENT OF THE CANCENIA, LOAD WUTT HE MERTICAL TO ANY	C. STORY LINKS	KENG REPORT		ETO CORIDA	Canada a series a s
14. 00 NOT CLIME ON LACING AND IMAGING.	<ol> <li>USE SCHEW JACKS TO ADJUST FOR UNEXED CHADE SCHORTONS, TO LEVEL AND ACCURATELY PEOPTICK THE</li> </ol>	<ul> <li>EDIPHENT TO BE UPT IN POSITION FOR REMOVING SHOULD BE ORDERED INTRODUCED BY A GLASSED DECEMBER WORDENING SECOND ORDER OF DE COD.</li> </ul>		PONAL S	The Total State
15. SHORE PRAMES AND COMPONENTS MERE DESIDIED AS AN INTERCOM, STUTIEN AND SMALL NOT BE INTERNALD.	2 50 NET EXCESS SHORNE COMPANY'S RECOMMENDED	AS A PART OF RESIDENCE SYSTEM EXTERNE CARE MUST BE THAT'S TO RELATE THE ADJUSTMENT SCREWS		and the second	3,02,02,02,02,02,02,02,02,02,02,02,02,02,
SAFETY GUIDELINES:	WARNER DITENSION OF SORE JACK REP SORE JACK ENERGING TO A WARNER FOR WARNER LOND CAREFUL CARENTS	SERVICEON ME ASSAULTED TO DESI SPOLLO NEN HE TRANSMOL ONLY CONTROL TO AGAIN WALE WEN THE			UNAUT UNAUT
PROVING FOR GONCIDER FORWARDIN (PROVING SAFETY IS PUBLICATED INTO CONTRACTOR	3 wate certain TexT ALL SCIEW JACKS ARE FINALY IN	VACUTURE OF THE SLAD IN THIS WANTER THE FINAL RESISTING BELOW HEL NOT BE CAREFUL THE LOAD OF THIS SLAD THESE IS AN APPLICATION SAME.	9		5 8
EXEMPLES SATEN SERVICE UPON THE PROPER DECTOR	CONTACT WITH SHE FOUNDATION AND PRANE LECS.	NOTE 1	NOTO & SHORE DIG.		10m
INSPECT VICE OF SHORING BEFORE EACH USE TO SEE NAME THE ASSOCIATE HAS NOT BEEN ALXINED AND IS SAFE FOR	1. SPECIAL CONTREPARTON MUST BE GREN TO THE	(3.1) RETER TO THE GOMETHING CODES FOR YOUR JOB LOCATOR	60	Cite units, suits, Satisfar (LC, auroranteretationale)	States 20100047 States by Balance Clarks
YOUR LIKE SHORE SHEETY BALES IN A COMPOUND.	A WER SLOPE OF SUPPORTE BY SLOPEG LEDGES (STRACES)	SONG SUPPORT PEOPLE IN THE DANKST HE CALLED AND AND AND AND AND AND AND AND AND AN			5 E
PLACE AND BE SURE THAT ALL PERSONS AND EVECT USE. ON DISMANTLE SHOWING AND ADDATE OF THEM.	<ol> <li>MEN (ED(EX (STRUCH) HORT/WITH RATE DODDS 25 TO 1.</li> <li>MEN EXCEPTION LINEAR CONDENS PART.</li> </ol>	chips, sone (canel) weather and a second and a second seco	(1) NOW OF HORIZONTAL		TOM: NO
FOLDW ALL STATE, LOCK, AND REDENAL CODES, ONDRANCES AND REDULATIONS PERSONNES TO SHORML.	2. WEN LEDGE (STRACE) CONSETS OF WILTING WENDER O.E., SOURCE 246, 246, 275.3	RELARDENTS SHOW ELEMENT WHITHCTHEDS ARE REPORTED FOR REPORTED IN ANY PROJECT AND REPORTS	NOTIN CAREEN AND A REAL AND A REA		
ROPET AS EXPENDED RECORD USED AND THE ANY READER OF ANY	<ul> <li>Media HOHEDATA, SHORES AND PLACED OTHER THAN AT HEAT ANILES TO THER SLIPPORTS.</li> </ul>	CONST. OF ACTUAL TEST'S SATA AND CONSIDERATING CONSTRUCTIONS			DATE OR ON JUST
MEDING LOCKING DEVECS, ANY CONTOREST MICH CANNOT IN CONTACT WITH IN DRUGHT INTO PROPER ALCOMENT OF CONTACT WITH	2. ADDURE THAT BEARING ENDS OF THOMPS BEARS ARE IPEOPER'S TOUPPORTED AND THAT LODING TRADES ARE		200		AS-542MN 2446, D.Y. 22403, B
PT SHALL BE READED AND REPLACED.	BEARS.		5 5		PROJECT NO.
A DRUMENT LANDAT DARL DE AVALABLE AND USED DN THE ADD DTE AT ALL THES.	<ol> <li>INDELTATINE, SHORENO BEARD SHOLLD NUT BE SUPPORTED UDDET SHAR AT SHE BEARD PROVIDE UNEDST HELDANDREED BY YOUR SHOREN COMPARED.</li> </ol>		× 8		2108249
INSPECT EXECTED SHORING AND FORMING FOR CONFORMITY WITH LANDOT AND SAFETY PRACTICES PEOR TO POUR.	CANTERIES WHE DID' OF SHORE COMPANY HOMODINES BEAMS DELY, CANTERIES SHALL NOT EXCEED		<u>⊥_↓_</u> ↓		DRAMMO.
CONSULT YOUR SHOPPING COMPANY REPRESENTATIVE WHEN IN			TYPICAL STEEL POST SHORES		SH-00
COLUTE SMOWING IS OUR DUSINESS NEVER TWE CHANGES					Sheet 1 of 2









Codes:	Materials:	
<ol> <li>(1) FBC 2020, 7<sup>th</sup> Edition</li> <li>(2) ACI 318-14</li> <li>(3) ACI 530-13</li> <li>(4) ASCE 7-16</li> <li>(5) AISC (ASD 14th Ed.)</li> <li>(6) NDS 2018</li> <li>(7) ACI 347.2R-05. Guide for Shoring/Re-shoring of Concrete Multistory Buildings</li> <li>(8) ADM 1-2015</li> </ol>		

Table of Content:				
Page	Description			
1	Design criteria			
2	Design loads and wall bracing loading			
16	Bracing members check			
20	Adhesive anchors check			
22	Equipment capacity tables			

JOB NO. 2108249	SHEET NO.	
CALCULATED BY	DATE	8/23/21
CHECKED BY	DATE	

www.struware.com

### Code Search

Code: ASCE 7 - 16

### Occupancy:

Occupancy Group = B Business

### **Risk Category & Importance Factors:**

Risk Category =	п
Wind factor =	1.00
Snow factor =	1.00
Seismic factor =	1.00

### Type of Construction:

Fire Rating:

Roof =	0.0 hr
Floor =	0.0 hr

### **Building Geometry:**

Roof angle (θ)	0.00 / 12	0.0 deg
Building length	95.5 ft	
Least width	0.0 ft	
Mean Roof Ht (h)	10.5 ft	
Parapet ht above grd	10.5 ft	
Minimum parapet ht	0.0 ft	

### Live Loads:

Roof	0 to 200 sf:	20 psf
	200 to 600 sf:	24 - 0.02Area, but not less than 12 psf
	over 600 sf:	12 psf

#### Floor:

Typical Floor	40 psf
Partitions	15 psf
Lobbies & first floor corridors	100 psf
Corridors above first floor	80 psf
Balconies (1.5 times live load)	60 psf

7500 NW 25th ST Miami, FL 33155 305-477-8860 JOB TITLE Basement Wall Wind calculations

JOB NO.	2108249	SHEET NO.	
CALCULATED BY		DATE	8/23/21
CHECKED BY		DATE	

#### Wind Loads : ASCE 7-16 Ultimate Wind Speed 175 mph Nominal Wind Speed 135.6 mph **Risk Category** 11 **Exposure Category** D Enclosure Classif. **Open Building** Internal pressure +/-0.00 Directionality (Kd) 0.85 1.030 Kh case 1 Kh case 2 1.030 Type of roof Monoslope '(z) Topographic Factor (Kzt) Topography Flat Speed-up Hill Height 0.0 ft H< 15ft;exp D (H) x(downwind) x(upwind) Half Hill Length (Lh) 0.0 ft : Kzt=1.0 Actual H/Lh 0.00 = HZ Use H/Lh 0.00 = н Lh H/ Modified Lh = 0.0 ft 287 From top of crest: x = 0.0 ft Bldg up/down wind? downwind ESCARPMENT $K_1 = 0.000$ H/Lh= 0.00 $K_2 = 0.000$ V(z)x/Lh = 0.00z z/Lh = 0.00 $K_3 = 1.000$ Speed-up At Mean Roof Ht: V(z)x(upwind) x(downwind) $Kzt = (1+K_1K_2K_3)^2 = 1.00$ H/2 Н Lh H/2

	2D RIDGE	or 3D AXISYMMETRICAL	HILL
--	----------	----------------------	------

Gust	Effect	Factor
h	=	10.5 ft
B	=	0.0 ft
/z (0.6h)	=	7.0 ft

 $\label{eq:Flexible structure if natural frequency < 1 Hz (T > 1 second).$  If building h/B>4 then may be flexible and should be investigated.  $h/B = \# DIV/0! \qquad \# DIV/0!$ 

#### G = 0.85 Using rigid structure default

Rig	id Structure	Flexible or Dyn	amically Se	nsitive St	tructure		
ē =	0.13	$34 \ln y (\eta_1) =$	0.0 Hz				
ℓ = z <sub>min</sub> =	650 ft 7 ft	Damping ratio (β) = /b =	0 0.80				
c = g <sub>Q</sub> , g <sub>v</sub> =	0.13 3.4	/α = Vz =	0.11 172.8				
$L_z =$	535.5 ft	N <sub>1</sub> =	0.00				
Q =	0.97	R <sub>n</sub> =	0.000				
$I_z =$	0.16	R <sub>h</sub> =	28.282	η =	0.000	h =	10.5 ft
G =	0.91 use G = 0.85	R <sub>B</sub> =	28.282	η =	0.000		
		R <sub>L</sub> =	28.282	η =	0.000		
		g <sub>R</sub> =	0.000				
		R =	0.000				
		Gf =	0.000				

7500 NW 25th ST

Miami, FL 33155 305-477-8860

JOB NO.	2108249	SHEET NO.	
CALCULATED BY		DATE	8/23/21
CHECKED BY		DATE	

### Enclosure Classification

Test for Enclosed Building:	Ao < 0.01Ag or 4 sf, whichever

Test for Open Building:

All walls are at least 80% open. Ao ≥ 0.8Ag

Test for Partially Enclosed Building: Predominately open on one side only



is smaller

Conditions to qualify as Partially Enclosed Building. Must satisfy all of the following:

Ao ≥ 1.1Aoi

Ao > smaller of 4' or 0.01 Ag

Aoi / Agi ≤ 0.20

Where:

Ao = the total area of openings in a wall that receives positive external pressure.

Ag = the gross area of that wall in which Ao is identified.

Aoi = the sum of the areas of openings in the building envelope (walls and roof) not including Ao.

Agi = the sum of the gross surface areas of the building envelope (walls and roof) not including Ag.

Test for Partially Open Building:

A building that does not qualify as open, enclosed or partially enclosed. (This type building will have same wind pressures as an enclosed building.

### Reduction Factor for large volume partially enclosed buildings (Ri) :

If the partially enclosed building contains a single room that is unpartitioned, the internal pressure coefficient may be multiplied by the reduction factor Ri.

Total area of all wall & roof openings	(Aog):		0 sf
Unpartitioned internal volume (Vi) :			0 cf
		Ri =	1.00

### Ground Elevation Factor (Ke)

Grd level above sea level =	0.0 ft		Ke =	1.0000
Constant =	0.00256	Adj Constant = 0.00256		

	RC GROUP, LL	C			J	OB TITLE	Basement W	all Wind	calculations	
	Miami, FL 33155	5				JOB NO.	2108249		SHEET NO.	0/00/04
	305-477-8860				CALCUL CHE	CKED BY			DATE	8/23/21
Wind Loa	ads - Other Str	ucture	es:	ASCE 7- 16				Ultin	nate Wind Pr	essures
	Wind Gust Effect Fact	Factor = or (G) = Kzt =	1.00 0.85 1.00	Ultimate Wind Ex	Speed = posure =	175 D	mph			
A. Solid Fr	eestanding Walls	& Soli	d Signs	(& open sig s/h =	ns with I 1.00	ess th	an 30% op	en) Case A a	& B	
Dis	st to sign top (h)	10.5 ft		B/s =	9.10			Cf	= 1.31	
He	eight (s)	10.5 ft		Lr/s =	0.00		F = qz	G Cf As	= 76.4 A	s
Wi	idth (B)	95.5 ft		Kz =	1.030			As	= 0.0 s	f
Wa Dir	all Return (Lr) = rectionality (Kd)	0.85		qz =	68.7 p	osf		F	= 0 lk	os
Pe	rcent of open area		Open r	eduction				Case	C	
	to gross area	0.0%		factor =	1.00	H	oriz dist from ndward edge	Cf	- F=qzGCfAs (	psf)
			Case C re	duction factors			0 to s	2.93	170.8 A	s
			Factor if	s/h>0.8 =	0.80		s to 2s	1.89	110.2 A	s
			Wall return	n factor			2s to 3s	1.41	82.1 A	s
			for Cf	at 0 to s =	1.00		3s to 10s	0.80	46.5 A	S

### B. Open Signs & Single-Plane Open Frames (openings 30% or more of gross area)

Height to centroid of Af (z)	0.0 ft			Kz =	1.030
				Base pressure (qz) =	68.7 psf
Width (zero if round)	1.0 ft				
Diameter (zero if rect)	0.0 ft			$F = q_z G C_f A_f =$	0.0 Af
Percent of open area		1 =	0	Solid Area: Ar =	10.0 sf
to gross area	0.0%	$C_{t} =$	2	F =	0 lbs
Directionality (Kd)	0.85			Design sign	as solid sign

3. Where soil has a very low friction coefficient, or for some clay subsoils where cohesion is low or unreliable, and the required depth of key is impracticable, the base may be supported on battered piles.

\* Larger of: Class B for M and ld for O











Fig. 14-4 Designs to Prevent Horizontal Sliding

Q

0

3

0

¥1

\$

No

11

4º

Soil Data and Assumed Properties. Three classes of soil are considered as backfill and bearing. See Table 14-1. Class A would qualify as nearly ideal backfill – easily drained and creating least lateral pressure, 30h (psf), where h is height, in feet, below top of wall. Class B, 45h (psf), includes many more naturally occurring combinations of soils suitable for engineering purposes. Class C level backfill is equivalent to water pressure, 62.5h (psf). It may include mixtures of various compositions of actual soils in place or even allow for partial height water tables in Class A or Class B backfills.

SET.	SET.	Y	¢	μ	Hori	Horizontal		Sloping	Rockfill*	29
class Max. of wt. Soll pst	Internal	Friction	PTE	STURE	Active	Active	Slo	pe		
	pst	st Friction	n Silding	Silding pst	pst	pst pst	Horiz. Comp.	Comp.	Angle A	Coten
	105 135 132	≥33°-45' ≥30° ≥20°-56°	0.55 0.55 0.45	30h 45h 62.5h	368h 405h 279b	60h 70h	30h 40h 45b	33°-41' 29°-45' 18°-26'	1%:1 1%:1 3-1	

Table 14-1 Soil Properties Used for Design

Class A includes clean sand, gravel, broken stone, free of fines that might obstruct free drainage.

Class B includes granular soils, mixed grain sizes, dense enough to cause low permeability.

**Class C** includes fine, silty sands; granular soils with some clay; some glacial tills. Note that the basic horizontal pressure is liquid pressure. Class C backfill designs will also suffice for some combinations of Class A or Class B soils, with partial height water table, thus extending applicability of these designs.

### COST CONSIDERATIONS IN WALL DESIGN

Less Thickness – More Flexural Steel. Use of the minimum thickness structurally possible for walls principally reinforced for bending in one direction seldom achieves overall economy. The cost of reinforcing steel is a major item in the total cost. With the larger cover required for sanitary structures and even with single curtains of reinforcing steel in both directions, wall thicknesses less than 8 inches are likely to make concrete placing difficult and consolidation without honeycomb uncertain. Suggested designs here show 8 inches thicknesses for minor walls with heights,  $h_w$ , up to 7'. As walls become higher or more heavily loaded, greater thicknesses become economical, achieving reduction in weight of flexural steel directly proportional to increases in effective

\*\*Sloping Backfill" designs are conservatively based upon values from the AREA Manual chart. See Figure 14-5. From table 14-1 CRSI, Class of soil, see the ka calc's bellow:

For this project, south Florida sandy soils, Soil class B

$$\phi_1 := 30 \deg \qquad k_{a1} := \tan \left( 45 \deg - \frac{\phi_1}{2} \right)^2 = 0.33$$

Set of	γ φ μ Horizontal		Y	¢	1.303	Sloping	Rockfill*	12	
Class	Max. wt.	Max. Friction Pressure wt. Internal for Active Pas pst Friction Silding psf p	nternal for riction Silding psf psf	Internal for Active Passive part	Decelus	Active	Active	Slo	pe
Soll	pst				pat	Comp.	Comp.	Angle A	Coten
ABC	105 135 132	≥33°-45′ ≥30° ≥20°-56°	0.55 0.55 0.45	30h 45h 62.5h	368h 405h 279h	60h 70b 90h	30h 40h 45h	33°-41' 29°-45' 18°-26'	1½:1 1¾:1 3:1

### Table 14-1 Soil Properties Used for Design

Class A includes clean sand, gravel, broken stone, free of fines that might obstruct free drainage.

Class B includes granular soils, mixed grain sizes, dense enough to cause low permeability.

**Class C** includes fine, silty sands; granular soils with some clay; some glacial tills. Note that the basic horizontal pressure is liquid pressure. Class C backfill designs will also suffice for some combinations of Class A or Class B soils, with partial height water table, thus extending applicability of these designs.

#### AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS

#### (3.11.6.4-1)

where:

- $\Delta_p$  = constant horizontal earth pressure due to live load surcharge (ksf)
- $r_s = \text{total unit weight of soil (kcf)}$
- k = coefficient of lateral earth pressure
- $h_{eq}$  = equivalent height of soil for vehicular load (ft)

Equivalent heights of soil,  $h_{eq}$ , for highway loadings on abutments and retaining walls may be taken from Tables 3.11.6.4-1 and 3.11.6.4-2. Linear interpolation shall be used for intermediate wall heights.

The wall height shall be taken as the distance between the surface of the backfill and the bottom of the footing along the pressure surface being considered.

### Abutments

KETAINING Walls

Table 3.11.6.4-1—<u>Equivalent Height of Soil for Vehicula</u>r Loading on Abutments Perpendicular to Traffic

Abutment Height (ft)	$h_{eq}$ (ft)
5.0	4.0
10.0	3.0
≥20.0	2.0

 Table 3.11.6.4-2—Equivalent Height of Soll for Vehicular

 Loading on Retaining Walls Parallel to Traffic

ſ	at some states of the dead	$h_{eq}$ (ft) Distant backface to	ance from wall edge of traffic
	Retaining Wall Height (ft)	0.0 ft	1.0 ft or Further
ľ	5.0	5.0	2.0
1	10.0	3.5	2.0
t	≥20.0	2.0	2.0

The load factor for both vertical and horizontal components of live load surcharge shall be taken as specified in Table 3.4.1-1 for live load surcharge.

#### 3.11.6.5-Reduction of Surcharge

If the vehicular loading is transmitted through a structural slab, which is also supported by means other than earth, a corresponding reduction in the surcharge loads may be permitted.

- Poisson's ratio for the pavement and subgrade materials are 0.2 and 0.4, respectively
- Wheel loads were modeled as a finite number of point loads distributed across the tire area to produce an equivalent tire contact stress
- The process for equating wall moments resulting from the elastic solution with the equivalent surcharge method used a wall height increment of 0.25 ft.

The value of the coefficient of lateral earth pressure k is taken as  $k_o$ , specified in Article 3.11.5.2, for walls that do not deflect or move, or  $k_o$ , specified in Articles 3.11.5.3, 3.11.5.6 and 3.11.5.7, for walls that deflect or move sufficiently to reach minimum active conditions.

The analyses used to develop Tables 3.11.6.4-1 and 3.11.6.4-2 are presented in Kim and Barker (1998).

The values for  $h_{eq}$  given in Tables 3.11.6.4-1 and 3.11.6.4-2 are generally greater than the traditional 2.0 ft of earth load historically used in the AASHTO specifications, but less than those prescribed in previous editions (i.e., before 1998) of this specification. The traditional value corresponds to a 20.0-kip single unit truck formerly known as an H10 truck, Peck et al. (1974). This partially explains the increase in  $h_{eq}$  in previous editions of this specification. Subsequent analyses, i.e., Kim and Barker (1998) show the importance of the direction of traffic, i.e., parallel for a wall and perpendicular for an abutment on the magnitude of  $h_{eq}$ . The magnitude of  $h_{eq}$  is greater for an abutment than for a wall due to the proximity and closer spacing of wheel loads to the back of an abutment compared to a wall.

The backface of the wall should be taken as the pressure surface being considered. Refer to Article C11.5.5 for application of surcharge pressures on retaining walls.



This Article relates primarily to approach slabs which are supported at one edge by the backwall of an abutment, thus transmitting load directly thereto.

 $\Delta_p = k \gamma_s h_{ss}$ 

3-130

# TRUCKS

### LIVE LOAD SURCHARGE, LS (3.11.6.1):

- If vehicular load is expected on the surface of the backfill within a distance equal to one half the wall height behind the back face of wall, a live load surcharge must be applied.
   Hwalt/2 = Distance Live Lobp
   The horizontal pressure due to live load surcharge, Δ<sub>n</sub> (ksf), can be estimated
- The horizontal pressure due to live load surcharge,  $\Delta_p$  (ksf), can be estimated using Equation 3.11.6.4-1 as:

$$\Delta_p = k \gamma_s h_{eq} \quad (KSF)$$

5.02.00

LS = LINE LOAD Surcharge

- k = Coefficient of lateral earth pressure
- $\gamma_s = \text{Unit weight of soil } (kcf)$

 $h_{eq}$  = Equivalent height of soil for vehicular load (ft)

	Table 3.11.6.4-1: Equivalent	Height of Soil for Ve endicular to Traffic	PER
1	Abutment height ( <i>ft</i> )	$h_{eq}(ft)$	TRA
ea	5.0	4.0	
Ŧ	10.0	3.0	

≥ 20.0

PERPENDICULAR TRAFFIC

Ap=	Kyheq

DGE

Table 3.11.6.4-2:	Equivalent Height	of Soil for Vehicular Loading on
Retaining Walls p	arallel to Traffic	PARALLEL Trafico

	$\frac{h_{eq}(ft)}{Distance from wall back face to edge of traffi$			
Retaining Wall Height (ft)	0.0 ft	≥ 1.0		
5.0	5.0	2.0		
10.0	3.5	2.0		
≥ 20.0	2.0	2.0		



Dr. Foued Zayati, Ph.D., S.E., P.E., EETUSA.COM

RC GROUP, LLC Structural & Shoring Consulting Engineers

3-130

where:

Street live load truck surcharge for wall parallel to highway load, for collins avenue basement walls.

By inpection, loading along Collins Ave. will control check since the other three side streets have local traffic accessing building notrh and south of the site.

As per AASHTO formula 3.11.6.4-1, and Table 3.11.6.4-2, the highway live surcahrge load is

(3.11.6.4-1)

 $A_{\mu} = k\gamma_{\mu}h_{\mu\mu}$ 

Soil class C, conservative, see previous pages

- $\Delta_p$  = constant horizontal earth pressure due to live load surcharge (ksf)
- total unit weight of soil (kcf) Υ.,
- k coefficient of lateral earth pressure
- $h_{eq}$  = equivalent height of soil for vehicular load (ft)

Equivalent heights of soil,  $h_{eq}$ , for highway loadings on abutments and retaining walls may be taken from Tables 3.11.6.4-1 and 3.11.6.4-2. Linear interpolation shall be used for intermediate wall heights.

The wall height shall be taken as the distance between the surface of the backfill and the bottom of the footing along the pressure surface being considered.

30deg 
$$k_a := tan \left( 45deg - \frac{\Phi}{2} \right)^2 = 0.33$$

 $\gamma_{\text{SoilMax}} := 135 \text{pcf}$ 

$$k_a = 0.33$$

Table 3.11.6.4-2-Equivalent Height of Soil for Vehicular Loading on Retaining Walls Parallel to Traffic

a cal maintain a bar	haq (ft) Distance from we backface to edge of traff			
Retaining Wall Height (ft)	0.0 ft	1.0 ft or Further		
5.0	5.0	2.0		
10.0	3.5	2.0		
≥20.0	2.0	2.0		

as per table to the left, it is conservative to say that the truck wheels will fall adjacent to the sidewalk gutter which is approximately 6ft away from the wall's back side.

 $h_{eq} := 2$ 

φ:=

 $\Delta_p := k_a \cdot \gamma_{SoilMax} \cdot h_{eq} \cdot (1 \text{ ft}) = 90 \text{ psf}$   $\Delta_p = 0.09 \text{ ksf}$  per linear foot



Page 10 of 35



RC GROUP, LLC Structural & Shoring Consulting Engineers

DESIGN CRITERIA:

- BASEMENT SHEET PILLING WALL WILL TO CARRY LOADS WHEN TEMPORARY BRACING RESTORES ORIGINAL WALL TOP LATERAL SUPPORT CONDITION. ANY LOOSE CONCRETE COVER SHALL BE REMOVED AND BRACING TOP PLATE SHALL BE ATTACHED DIRECTLY TO SHEET PILLING
- BASED ON EXISTING STRUCTURAL DRAWINGS BASEMENT WALL CONSTRUCTION, OUR SITE VISITS AND OUR ENGINEERING JUDGEMENT, EXISTING BASEMENT WALL WILL BE ADEQUATE FOR TRANSFERRING THE TOP OF WALL LOADS TO BRACES, SINCE THE BRACES ARE SPACED AT SUCH CLOSED DISTANCE THAT WILL RESEMBLE THE CONTINUOUS SUPPORT PROVIDED BY THE DEMOLISHED FIRST ELEVATED CONCRETE SLAB.
- EXISTING FIRST ELEVATED CONCRETE SLAB'S REMAINING STEEL REINFORCEMENT HANGING AT TOP OF EXISTING BASEMENT WALL SHALL BE AVOIDED AND/OR REMOVED TO GIVE WAY TO BRACING SYSTEM TOP ATTACHMENTS.
- ROAD BARRIERS WILL BE INSTALLED (MOT), BY OTHERS, AT A DISTANCE SHOWN ON OUR PLANS FOR REFERENCE, THAT WILL PREVENT ROADWAY USERS FROM FALLING INTO OPEN BASEMENT AND TO COMPLY WITH SAFETY PLAN PROVIDED BY OTHERS.
- WE WILL USE A LIVE LOAD VEHICULAR TRAFFIC SURFACE HORIZONTAL SURCHARGED LOAD, AGAINST EXISTING BACK OF BASEMENT WALL, BASED ON ASHTO 3.11.6.1, FORMULA 3.11.6.4-1 AND TABLE 3.11.6.4-2.
- BRACING AND RE-SHORING WILL BE DESIGNED FOR ALL APPLICABLE CODE LOADS FOR THE PRESENT CONDITION OF THE REMAINING STRUCTURE ABOVE MENTIONED. DUE TO THE LENGTH OF TIME THAT THIS EQUIPMENT WILL BE INSTALLED IN THIS SITE, WE WILL USE CODE LOADS FOR PERMANENT STRUCTURES.
- 7. EXISTING CONCRETE STRUCTURAL BASEMENT SLAB WILL BE USED TO SUPPORT TEMPORARY BRACING SYSTEM HORIZONTAL AND VERTICAL REACTION. DILAPIDATED AND/OR SPALLED SURFACES SHALL BE AVOIDED.
- 8. AS PER EXISTING STRUCTURAL PLANS, EXISTING CONCRETE STRUCTURAL SLAB IS 9" THICK. THIS VALUE IS CONSISTANT WITH THE AVERAGE VALUE MEASURED ON THE FIELD. BASED ON OUR VISUAL FIELD OBSERVATIONS, THIS STRUCTURAL SLAB APPEARS TO BE IN GOOD CONDITION AND SUPPORTED DEBRIS FROM ENTIRE BUILDING AFTER COLLAPSING.
- 9. NO STAGNANT WATER AT EXISTING CONCRETE STRUCTURAL BASEMENT SLAB, WATER REMOVAL BY OTHERS.
- 10. MAXIMUM BRACING SPACING WILL BE CALCULATED AND SHOWN ON PLANS.
- 11. EXISTING ROADWAY DRAINAGE PRE-FABRICATED PRE-ENGINEERED CATCH BASIN BOX WILL BE BYPASSED.

### RC GROUP, LLC Structural & Shoring Consulting

Engineers



Project Title: Engineer: Project Descr:

Project ID:

								Print	ed: 17 AUG 2	021, 2:50PM
<b>General Bean</b>	n Analysis			192.168.10.10	data1\Engineering	2021/2108	249-CHAMPLAIN TOWER-MIAM ENERCALC, INC. 198	II POLICE-BOF 3-2017, Build:6	AM\calcs s .17.3.29, Ve	urfside.ec6 er.6.17.3.31
.ic. # : KW-0601146	2							Licensee :	RC GR	OUP, LL
Description : Con	trolling case - Brace top	plate Reaction	Along Colins	ave.						
General Beam Pro	perties									
Elastic Modulus	29,000.0 ksi									
Span #1	Span Length =	9.660	ft	Area =	100	.0 in^2	Moment of Inertia	= 1	1,000.0	in^4
Span #2	Span Length =	0.830	ft	Area =	100	.0 in^2	Moment of Inertia	= 1	1,000.0	in^4
177										
				L(0.09)					Dio	05 0
*	*			D(0.684.0.05)			*		YYL	TT
<u>×</u>	*		Ŧ	W(0.048)	*		*		y wo	0.048)
_				•						•••
			5	Span = 9.660 ft					Span =	0.830 ft
Applied Loads					Service	loads er	ntered. Load Factors wi	ll be applie	d for cal	culations
Load for Span Num	nber 1									
Uniform Load Varying Unifor Uniform Load Load for Span Num Uniform Load	: W = 0.0480 k/ft, Tr rm Load : D(S,E) = 0 : L = 0.090 k/ft, Trib nber 2 : W = 0.0480 k/ft, Tr	ibutary Width = .6840->0.050 k utary Width = 1 ibutary Width =	: 1.0 ft, (wind) /ft, Extent = 0 .0 ft, (LL Veh : 1.0 ft, (wind)	) ).0>> 9.6i iicular) )	60 ft, Trib Wid	ith = 1.0 t	t, (Soil)			
Uniform Load Varying Unifor	: L = 0.090 k/ft, Trib rm Load : D(S,E) = 0	utary Width = 1 .050->0.0 k/ft, I	.0  ft, (LL  Veh)	icular) ->> 0.830 fl	t, Trib Width =	= 1.0 ft, (L	L vehicular)			
DESIGN SUMMAR	Y									
Maximum Bendir	ng =		5.559 k	k-ft Ma	aximum She	ear =			3.28	39 k
Load Combination	n		+D+L+H		Load Co	mbinatio	n		+D+L	+H
Location of maxim	num on span		0.000 fi	0.000 ft Location of maximum on span				0.0	00 ft	
Span # where ma	ximum occurs		Span # 1		Span # v	where ma	iximum occurs		Span #	<i>‡</i> 1
Maximum Deflec	tion		0.000		0					
Max Upward Tra	ansient Deflection		0.000 ir	n	0					
Max Downward	Total Deflection		0.001 ir	n	99078					
Max Upward Tot	tal Deflection		-0.000 ir	n	55206					
Maximum Forces &	& Stresses for Loa	ad Combinat	ons						(0)	
bad Combination	Span # Max	Stress Ratios	Mmax +	Mmax	Summary of Mo	ment Valu	Max/Omega Ch Pm	Sumr Va Max	nary of Sh	ear Value
Segment Length		VI V	williax +	- Xbillivi	wa - wax	MILX	milwoniega ob rtfl	va Max	VIIX	VIIVUIIE
Dsgn. L = 9.66 ft	1		2.65	-5.56	5.56			3.29		
Dsgn. L = 0.83 ft	2			-0.04	0.04			0.10		
Dsan L = 9.66 ft	1		2.08	-4.52	4.52			275		
Dsgn. L = $0.83$ ft	2		2.00	-0.01	0.01			0.02		
)+L+H	4		0.05	5.50	5.50			2.00		
$Dsgn. L = 9.66 \pi$ Dsgn. L = 0.83 ft	2		2.65	-0.04	0.04			3.29		
H+Lr+H								5.15		
Dsgn. L = $9.66$ ft	1		2.08	-4.52	4.52			2.75		
)+S+H	2			-0.01	0.01			0.02		
Dsgn. L = 9.66 ft	1		2.08	-4.52	4.52			2.75		
Dsgn. L = 0.83 ft	2			-0.01	0.01			0.02		
Dsgn. L = 9.66 ft	1		2.50	-5.30	5.30			3.15		
Dsgn. L = 0.83 ft	2			-0.03	0.03			0.08		
1+0.750L+0.750S+H	1		2.50	.5 30	5 30			3 15		
Dsgn. L = 0.83 ft	2		2.00	-0.03	0.03			0.08		
+0.60W+H										
Dsgn. L = 9.66 ft Dsgn. L = 0.82 ft	1		2.26	-4.86	4.86			2.92		
)+0.70E+H	2			-0.02	0.02			0.04		
Champlain 66 qwers	South+ Existing Ba	asement Tem	porary 2018 I	Bracing	aluations2			2.75	Page 1	14 of 35

Project ID:

### **General Beam Analysis**

Printed: 17 AUG 2021, 2:50PM

192.168.10.10/data1\Engineering\2021\2108249-CHAMPLAIN TOWER-MIAMI POLICE-BOFAM\calcs surfside.ec6

ENERCALC, INC. 1983-2017, Build 6.17.3.29, Ver.6.17.3.31 Licensee : RC GROUP, LLC

Lic. # : KW-06011462
Description : Controlling case - Brace top plate Reaction - Along Colins ave.

Load Combination		Max Stress Ratios Summary of Moment Values					ues			Summ	ary of Sh	near Values	
Segment Length S	Span #	M	V	Mmax +	Mmax -	Ma - Max	Mnx	Mnx/Omega	Cb	Rm	Va Max	Vnx	Vnx/Omega
Dsgn. L = 0.83 ft	2				-0.01	0.01					0.02		
+D+0.750Lr+0.750L+0.450W+H	1												
Dsgn.L = 9.66 ft	1			2.64	-5.55	5.55					3.28		
Dsgn. L = 0.83 ft	2				-0.04	0.04					0.09		
+D+0.750L+0.750S+0.450W+H				12.01	121201	12/22/							
Dsgn. L = 9.66 ft	1			2.64	-5.55	5.55					3.28		
Dsgn. L = 0.83 ft	2				-0.04	0.04					0.09		
+D+0.750L+0.750S+0.5250E+H													
Dsgn.L = 9.66 ft	1			2.50	-5.30	5.30					3.15		
Dsgn. L = 0.83 ft	2				-0.03	0.03					0.08		
+0.60D+0.60W+0.60H													
Dsgn.L = 9.66 ft	1			1.43	-3.05	3.05					1.82		
Dsgn. L = 0.83 ft	2				-0.01	0.01					0.04		
+0.60D+0.70E+0.60H													
Dsgn.L = 9.66 ft	1			1.25	-2.71	2.71					1.65		
Dsgn. L = $0.83$ ft	2				-0.00	0.00					0.01		
Overall Maximum Defle	ections	1											
Load Combination		Span	Max. "-" Defl	Location	n in Span	Load Comb	pination			Max.	"+" Defl	Locatio	n in Span
+D+L+H		1	0.0012		5.424						0.0000		0.000
		2	0.0000		5.424	+D+L+H					0.0004		0.830
Vertical Reactions					Suppor	t notation : Far I	eft is #1			Values in	KIPS		
Load Combination		Support 1	Support 2	Suppor	t3								
Overall MAXimum		3.289	1.221										
Overall MINimum		0.287	0.216										
+D+H		2.751	0.815										
+D+L+H		3,289	1,221										
+D+Lr+H		2 751	0.815										
+D+S+H		2 751	0.815										
+D+0 7501 r+0 7501 +H		3 155	1 1 1 9										
+D+0.750L+0.750S+H		3 155	1 1 10										
+D+0.000L+0.003+H		2 0 2 2	0.045										
+D+0.00W+H		2.923	0.945										
+D+0.70E+H		2.751	0.815										
+D+0.750Lr+0.750L+0.450V	V+H	3.284	1.217										
+D+0.750L+0.750S+0.450W	/+H	3.284	1.217										
+D+0.750L+0.750S+0.5250	E+H	3.155	1.119										
+0.60D+0.60W+0.60H		1.823	0.619										
+0.60D+0.70E+0.60H		1.650	0.489										
D Only		2.751	0.815										
Lr Only													
L Only		0.539	0.406										
S Only													
W Only		0 287	0.216										
E Only		0.201	V.6. IV.										
L Only													
H Olly													

Structural & Shoring Consulting Engineers

### MEADOW BURKE WALL BRACES - BASEMENT

Brace length and safe working loads, using steel braces, see attached capacity table and spec's:

 $W_{walltielocation} := D_{toppanelelevation} - 10in = 9.667 ft$ 

 $h_{wall} := 10.5 ft$  wall actual height

 $\theta := 47 \text{deg}$   $h := \frac{W_{\text{walltielocation}}}{\sin(\theta)} = 13.22 \text{ ft}$  maximum

### Allowable Safe Axial (tension/compression) Working Load, MB 8-14

See attached brace capacity table,

$$A_{\text{brace}} \coloneqq \frac{518.4}{13.22^{1.74}} \cdot k \cdot \frac{1}{1.50} = 3.869 \cdot k$$

Horizontal force on this top of wall

 $F_{H} := 1221 plf$ 

$$F_{axial} \coloneqq \frac{F_H}{\cos(\theta)} = 1790.327 \frac{lb}{ft}$$

total wind horizontal force on all braces

Check brace:

we are using

n<sub>bracesquantity</sub> := 1

$$F'_{braceAxialL} := \frac{F_{axial}}{n_{bracesquantity}} = 1790.327 \frac{lb}{ft}$$

BraceSpacing := 2ft

F'braceAxial := F'braceAxialL BraceSpacing = 3.581 ·k

per brace

 $Check(A_{brace}, F'_{braceAxial}) = "OK"$ 

Structural & Shoring Consulting Engineers

hwall := 10.5ft wall actual height

### PERI WALL BRACES - BASEMENT

Brace length and safe working loads, using steel braces, see attached capacity table and spec's:

 $W_{walltielocation} := D_{toppanelelevation} - 10in = 9.667 ft$ 

 $\theta := 60 \text{deg}$   $h := \frac{W_{\text{walltielocation}}}{\sin(\theta)} = 11.16 \text{ ft}$  maximum

 $11.16ft = 3.4 \cdot m$ 

Allowable Safe Axial (tension/compression) Working Load, RSS II

See attached brace capacity table,

$$19$$
kN =  $4.271 \times 10^3$  lbf

$$A_{brace} := 42711b$$

Horizontal force on this top of wall

 $F_{H} := 1221 plf$ 

$$F_{axial} \coloneqq \frac{F_H}{\cos(\theta)} = 2442 \frac{lb}{ft}$$

total wind horizontal force on all braces

Check brace:

we are using

n<sub>bracesquantity</sub> := 1

$$F'_{braceAxialL} := \frac{F_{axial}}{n_{bracesquantity}} = 2442 \frac{lb}{ft}$$

BraceSpacing := 2ft

 $F'_{braceAxial} := F'_{braceAxialL} \cdot BraceSpacing = 4.884 \cdot k$ 

per brace

Check(A<sub>brace</sub>, F'<sub>braceAxial</sub>) = "OK as per ASCE 7, 1/3 Increased capacity for Load Combo Used"

Structural & Shoring Consulting Engineers

### PERI WALL BRACES - BASEMENT Brace length and safe working loads, using steel braces, see attached capacity table and spec's: Top brace information D<sub>toppanelelevation</sub> := 10.5ft hwall := 10.5ft wall actual height $W_{wall tielocation} := D_{toppanelelevation} - 10in = 9.667 \text{ ft}$ $h := \frac{W_{\text{walltielocation}}}{\sin(\theta)} = 13.67 \text{ ft} \text{ maximum}$ $h = 4.167 \cdot m$ $\theta := 45 \text{deg}$ Allowable Safe Axial (tension/compression) Working Load, SLS 320/420 See attached brace capacity table, Abrace := 12960.236lb 57.65kN = 12960.236 lbf $F_H := 1221 plf$ Horizontal force on this top of wall $F_{axial} := \frac{F_H}{\cos(\theta)} = 1726.755 \frac{lb}{ft}$ total wind horizontal force on all braces $n_{bracesquantity} := 1$ $F'_{braceAxialL} := \frac{F_{axial}}{n_{bracesquantity}} = 1726.755 \frac{lb}{ft}$ Check brace: we are using BraceSpacing := 5ft F'braceAxial := F'braceAxialL·BraceSpacing = 8.634·k per brace Check(Abrace, F'braceAxial) = "OK" CONTROLLING ANCHOR BOLTS LOADING: After carefull review of braces end forces reactions (load on anchors) this particular brace assembly reactions controls anchor bolts check. The loads are shown below. $(F_{axial}) \cdot sin(\theta) \cdot BraceSpacing = 6.105 \cdot k$ Vertical load per brace. $(F_{axial}) \cdot \cos(\theta) \cdot BraceSpacing = 6.105 \cdot k$ Horizontal load per brace.

Structural & Shoring Consulting Engineers

PERI WALL BRACES - BASEMENT

### Brace length and safe working loads, using steel braces, see attached capacity table and spec's: Top brace information D<sub>toppanelelevation</sub> := 10.5ft hwall := 10.5ft wall actual height $W_{wall tielocation} := D_{toppanelelevation} - 10in = 9.667 \text{ ft}$ $h := \frac{W_{\text{walltielocation}}}{\sin(\theta)} = 13.67 \text{ ft} \text{ maximum}$ $h = 4.167 \cdot m$ $\theta := 45 \text{deg}$ Allowable Safe Axial (tension/compression) Working Load, SLS 380/480 See attached brace capacity table, 67.6kN = 15197.085 lbf $A_{brace} := 15197lb$ $F_H := 1221 plf$ Horizontal force on this top of wall $F_{axial} := \frac{F_H}{\cos(\theta)} = 1726.755 \frac{lb}{ft}$ total wind horizontal force on all braces $n_{bracesquantity} := 1$ $F'_{braceAxialL} := \frac{F_{axial}}{n_{bracesquantity}} = 1726.755 \frac{lb}{ft}$ Check brace: we are using BraceSpacing := 5ft F'braceAxial := F'braceAxialL·BraceSpacing = 8.634·k per brace Check(Abrace, F'braceAxial) = "OK" CONTROLLING ANCHOR BOLTS LOADING: After carefull review of braces end forces reactions (load on anchors) this particular brace assembly reactions controls anchor bolts check. The loads are shown below. $(F_{axial}) \cdot sin(\theta) \cdot BraceSpacing = 6.105 \cdot k$ Vertical load per brace. $(F_{axial}) \cdot \cos(\theta) \cdot BraceSpacing = 6.105 \cdot k$ Horizontal load per brace.

**RC GROUP, LLC** Structural & Shoring Consulting Engineers

3/4" Dia. HILTI HY200 Adhesi Embedment, into 3,000 psi (mi	ve Anchor with HAS Rod, with 6 3/4" n.) concrete	
Loading:	Quantity of	f bolts to be used $n_{bolt} \coloneqq 1$
See previous page for controll	ig brace reactions.	
$T_{actual} := 6.105  k$ Upward c	n bolt Specing :	- 6in minimum
V <sub>perp</sub> := 0lb Shear on Perpendi	bolt cular to Member	
$V_{parallel} := 6.105 \text{ k}$ Shear on b	olt. Parallel to Member. for load calc's see previo	bus page
Connector Capacity:		
See attached manufacturer table	95.	
	EdgeDistance := 10in	
$E := 6in + \frac{0}{8}in \qquad E = 6 \cdot in$	ED := 1.5E ED = $9 \cdot in$ SD := 1.0·E SD = $6 \cdot in$	
Reduction Factors due to edge	listance and spacing:	
Spacing (Tension & Shear):	$R_s := if\left(\frac{Spacing}{SD} < 1.0, \frac{Spacing}{SD}, 1.0\right) = 1$	
Edge distance (Tension):	$R_{et} := if \left( \frac{EdgeDistance}{ED} < 1.0, \frac{EdgeDistance}{ED} \right)$	1.0 = 1
Edge distance (Shear):	$R_{ev} := if \left( \frac{EdgeDistance}{ED} < 1.0, \frac{EdgeDistance}{ED} \right)$	(1.0) = 1
Field condition: At one area of the basement exposing steel sheet pilling. a below for weld check.	wall, one portion of the top of the wall concrete wa t this location weld braces top plate to existing sho	as pryed-out eet piling. See
$P_{weldAllow} \coloneqq 3.71 \frac{k}{in} \cdot 2i$	$n \cdot 2 = 14.84 \cdot k$ $P_{weld} := \sqrt{T_{actual}^2 + V_{para}}$	$\frac{2}{100} = 8.634 \cdot k$
	$Check(P_{weldAllow}, P_{weld}) = "OK"$	]

Structural & Shoring Consulting Engineers

HY200 Adhesive Anchor:  $\alpha_{ASD} \coloneqq 1.2 \cdot 0.20 + 1.6 \cdot 0.80 = 1.52$  As per Hilti manual section 2.4.6 using worst case possible of DL and LL loads distribution.  $N_{des} := 10615lb$  $V_{des} := 22860 lb$ cracked  $N_{desASD} := \frac{N_{des}}{\alpha_{ASD}} = 6983.553 \text{ lb}$ Tension  $V_{desASD} := \frac{V_{des}}{\alpha_{ASD}} = 15039.474 \, lb$ Shear  $T_{c} := N_{desASD} \cdot R_{s} \cdot R_{et} \cdot n_{bolt}$  $V_{c\_perp} := V_{desASD} \cdot (R_{s} \cdot R_{ev}) \cdot n_{bolt}$  $T_c = 6983.55 \cdot lb$  $V_{c_perp} = 15039 \, lb$  $V_{c_{parallel}} := V_{desASD} \cdot (R_s \cdot R_{ev}) \cdot n_{bolt}$  $V_c$  parallel = 15039.47 lb Using Parabola equation aproach:  $UC := \left(\frac{T_{actual}}{T_{c}}\right)^{\frac{5}{3}} + \left(\frac{V_{perp}}{V_{c} perp}\right)^{\frac{5}{3}} + \left(\frac{V_{parallel}}{V_{c} parallel}\right)^{\frac{5}{3}} UC = 1.02$ Check(1.0, UC) = "Close Enough (+/- 2.5%)"

# MeadowBurke®

### **Brace Load Table**

Brace Type	Brace Length [ft.] Min. / Max.	Ultimate Brace Buckling Load [kips]	Ultimate Brace Shoe Load [kips]
B/C/D	14.50 / 20.93	3,470 / L <sup>2.439</sup>	9.60
B / C / D [w/single knee brace & cross lace]	14.50 / 29.59	6,940 / L <sup>2.439</sup>	9.60
Little "G"	14.50 / 20.21	26,300 / L 2.963	7.80
Standard "G"	22.50 / 28.87	1,540,000 / L <sup>4.118</sup>	7.80
STD. "G" [w/single knee brace & cross lace]	22.50 / 28.87	2,350 / L <sup>1.759</sup>	7.80
Big "G"	24.00 / 38.25	27,700,000 / L <sup>4.81</sup>	7.80
Big "G" [w/single knee brace & cross lace]	24.00 / 38.25	8,250 / L <sup>1.944</sup>	7.80
Big "G" [w/double knee brace & cross lace]	24.00 / 38.25	4,290 / L 1.659	7.80
MB Precast Brace - (45218HD)	8.00 / 14.00	518.54 / L <sup>1.74</sup>	9.5
MB Precast Brace - HD (45218EHD)	8.00 / 14.00	48.75 – 3L	13.5
Super 17	17.00	13.00	13.00
Super 22	22.00	11.00	11.00
Super 22 + 5' Extension	27.00	8.85	11.00
Super 22 + 10' Extension	32.00	5.80	11.00
Super 32	32.00	13.50	13.50
Super 32 + 5' Extension	37.00	10.36	13.50
Super 32 + 10' Extension	42.00	8.042	13.50
Super 32 + 10' & 5' Extensions	47.00	7.037	13.50
Super 32 + 2-10' Extension	52.00	5.778	13.50
Super 42	42.00	16.05	16.05
Super 52	52.00	16.05	16.05

Notes:

1. "L" is the total brace length in feet.

2. The equations above for ultimate buckling loads are based on test results performed on the braces when they were placed at an angle of 60 degrees to horizontal. For brace angles between 45 and 60 degrees to horizontal, multiply the buckling load derived from the equations above by the factor "K".

$$K = \frac{(1390 + 47 0)}{4210}$$

Where  $\emptyset$  = Brace angle to horizontal in degrees.

Exception: K = 1 may be used for all "Super Braces" except for the Super 22 + 10' Extension.

3. Do not use brace loads greater than the ultimate brace shoe loads above. Always use the smaller of the two loads.

4. To determine the concentric brace working load, divide the governing load (brace shoe or buckling load) by the desired safety factor. A 1.5 minimum safety factor is recommended for temporary wind bracing of concrete tilt-up wall panels. Braces when used for other purposes or different types of applied loads may require higher safety factors. Safety factor shall be determined by the user.

### Temporary Panel Bracing – Super 17, 22, 32, 42, 52, 62



Super 17–62 Braces are used to temporarily support concrete panels to resist wind load until a permanent connection is made. The brace is anchored to a concrete floor slab, Deadman or an MB Brace Badger. The top foot attaches via an embedded brace insert.

Brace Type	Brace Length [ft.]	Brace Buckling Load [kips]	Ultimate Brace Shoe Load [kips]	Weight
Super 621	62.00	16.05	17.87	950 lbs.
Super 52	52.00	16.05	17.87	680 lbs.
Super 42	42.00	17.87	17.87	550 lbs.
Super 32 <sup>2</sup>	32.00	13.50	13.50	275 lbs.
Super 22 <sup>2</sup>	22.00	11.00	11.00	136 lbs.
Super 17	17.00	13.00	13.00	105 lbs.

1: Super 62 brace requires some extension assembly on site. Installation instructions on back. 2: Super 22 and Super 32 are available with 5ft and 10ft extensions. NOTE: Use of an extension listed above reduces brace buckling load.

- · Variety of sizes to brace panels from 10 ft to 94 ft in height
- · Braces can be used on the inside or outside of the structure
- · All braces have additional length adjustment to simplify final plumbing
- Complies to ASCE 37-02 and ASCE 7-10 regarding basic wind speeds
- Engineered to be used with Meadow Burke's Badger, Slam Anchor, MB Brace Bolt and Brace Insert.

### Call 877.518.7665 or visit MeadowBurke.com

Champlain Towers South - Existing Basement Temporary Wall Bracing Evaluation



Meadow Bage 23. of 35n
# MB 8-14 Brace



# To learn more, call us at 877.518.7665 or visit us online at MeadowBurke.com

					in the second second		
24	12.12	7.00	14.00				7.26
23	12.12	7.00	14.00			8.10	7.81
22	12.12	7.00	14.00			8.79	8.42
21	12.12	7.00	14.00		9.99	9.57	9.10
20	12.12	7.00	14.00	11.5	11.0	10.4	9.88
19	12.12	7.00	14.00	12.8	12.1	11.4	10.7
18	11.33	6.54	13.08	18.9	17.9	16.7	15.7
17	11.33	6.54	13.08	20.0	19.9	18.5	17.2
16	10.54	6.08	12.17	20.0	20.0	20.0	18.9
15	9.74	5.83	11.25	20.0	20.0	20.0	20.0
14	8.94	5.17	10.33	20.0	20.0	20.0	20.0
13	8.16	4.71	9.42	20.0	20.0	20.0	20.0
12	7.36	4.25	8.50	20.0	20.0	20.0	20.0
11	7.36	4.25	8.50	20.0	20.0	20.0	20.0
10	7.36	4.25	8.50	20.0	20.0	20.0	20.0
9	7.36	4.25	8.50	20.0	20.0	20.0	20.0
8	7.00	4.83	8.50	20.0	20.0	20.0	20.0
Н	٧	Х	L	S0	S2	S4	S6
	Installa	tion Dim	ensions				
		ME	Precast	TeleBrac	e (8' to 1	(4')	
n	v Installa	tion Dim ME	ensions Precast	TeleBrac	52 e (8' to 1	14')	30

Ultimate load: 48.75-3L KIP Maximum Tension: 13.5 KIP

MeadowBurke



Page 24 of

Champlain Towers South - Existing Basement Temporary Wall Bracing Evaluation



# T-14 Tilt-Up Wall Braces

The Dayton Superior T-14 Tilt-Up Wall Braces are all steel, heavy duty wall braces designed to quickly and easily align and brace tilt-up wall panels. Rough adjustment of the T-14 braces is easily accomplished by telescoping the pipes to the nearest incremental hole. Final adjustment is then achieved by simply turning the brace. Dayton Superior wall braces are available in numerous sizes to provide a continuous range of tilt-up panel heights of fifty feet or more. Refer to the chart below for additional information.



11		
Туре	Description	Minimum and Maximum Brace Length
B-1	On-Site Pipe Brace	7'-6" to 8'-10"
B-2	Regular Pipe Brace	13'-0" to 20'-6"
B-4	Heavy Duty Regular Pipe Brace	14'-6" to 23'-6"
8-5	Heavy Duty Long Pipe Brace	22'-6" to 39'-0"
B-6	Short Pipe Brace	10'-0" to 14'-0"
B-7	Short Jumbo Brace	17'-0" Fixed Length
B-8	Jumbo Brace	22'-0" Fixed Length
B-9	Jumbo Brace with 5'-0" Extension	27'-0" Fixed Length
B-10	Jumbo Brace with 10'-0" Extension	32'-0" Fixed Length
B-11	Tru-Itt Brace	25'-6' to 40'-0"
B-12	Jumbo 5-1/2"	32'-0" Fixed Length
B-14*	B-12 Jumbo Brace, 10'-0" Extension	42'-0" Fixed Length
B-15*	B-12 Jumbo Brace, 20'-0" Extension	52'-0" Fixed Length
B-16	B-12 Jumbo Brace, 5'0" Extension	37'-0" Fixed Length

#### To Order:

Specify: (1) quantity, (2) Name, (3) model.

Example:

200, T-14 Tilt-Up Wall Braces. Model B-8.

\* Note: Field assembly is required for B-14 and B-15 braces. B-11 Brace Available West Coast Only

## T-15 Pipe Brace Extensions

The Dayton Superior Pipe Brace Extensions are available for the B-8 and B-12 pipe brace models. The T-15 extension for the B-12 model extends the brace five feet or ten feet increments. Extensions for the B-8 brace are available in five feet and ten feet lengths.



#### To Order:

Specify: (1) quantity, (2) name, (3) model.

Example: 40, T-15 Pipe Brace Extension, 5' extension for B-8 braces.

Champlain Towers South - Existing Basement Temporary Wall Bracing Evaluation

# **Bracing Information**



# **T-16 Pipe Knee Brace**

The Dayton Superior T-16 Pipe Knee Brace is an all steel, 1-1/2" diameter knee brace available in 10'-6" and 14'-6" lengths. The T-16 knee brace is used in conjunction with the T-17 Swivel Coupler to add strength and stability to standard wall braces.

#### To Order:

Specify: (1) quantity, (2) name, (3) length. **Example:** 120, T-16 Pipe Knee Braces, 10'-6" long.



#### T-16 Pipe Knee Brace

# **T-17 Swivel Coupler**

The Dayton Superior T-17 Swivel Coupler is designed to attach standard 1-1/2" diameter knee braces to 2" or 2-1/2" diameter wall braces.

#### To Order:

Specify: (1) quantity, (2) name, (3) wall brace diameter.

Example:

120, T-17 Swivel Couplers for 2" wall braces.



#### **T-17 Swivel Coupler**

# **Brace Length and Safe Working Loads**

	B-1 On-Site Pipe Brace								
0	147			Safe Working Load					
D	vv	F	в	Without Knee Bracing					
9'-0"	6'-0"	4'-6"	7'-6"	6,500 lbs.					
9'-6"	6'-5"	4'-9"	7'-11"	6,500 lbs.					
10'-0"	6'-8"	5'-0"	8'-4"	6,500 lbs.					
10'-6"	7'-0"	5'-3"	8'-9"	6,500 lbs.					

		B-:	2 Regular Pipe E	Brace		
D W F   16'-0" 10'-8" 8'-0"   17'-0" 11'-4" 8'-6"   18'-0" 12'-0" 9'-0"   19'-0" 12'-8" 9'-6"   20'-0" 13'-5" 10'-0"   21'-0" 14'-1" 10'-6"			Safe Working Load			
D	w	F	В	Without Knee Bracing	With Knee Bracing	
16'-0"	10'-8"	8'-0"	13'-4"	5,800 lbs.	6,500 lbs.	
17'-0"	11'-4"	8'-6"	14'-2"	4,800 lbs.	6,500 lbs.	
18'-0"	12'-0"	9'-0"	15'-0"	4,200 lbs.	6,500 lbs.	
19'-0"	12'-8"	9'-6"	15'-10"	3,550 lbs.	6,500 lbs.	
20'-0"	13'-5"	10'-0"	16'-7"	3,150 lbs.	6,500 lbs.	
21'-0"	14'-1"	10'-6"	17'-5"	2,800 lbs.	6,500 lbs.	
22'-0"	14'-9"	11'-0"	18'-3"	2,500 lbs.	6,500 lbs.	
23'-0"	15'-5"	11'-6"	19'-0"	2,275 lbs.	6,500 lbs.	
24'-0"	16'-1"	12'-0"	19'-11"	1,975 lbs.	5,925 lbs.	

Note: Depending on panel thickness and height, a double mat of reinforcing steel may be required to resist the bending stresses of temporary wind loads.

SWL provides a minimum factor of safety of 1.5 to 1.

Danger! With knee bracing means that knee, lateral and end bracing must be installed in order to obtain SWL's shown. Champlain Towers South - Existing Basement Temporary Wall Bracing Evaluation



# Brace Length and Safe Working Loads

B-4 Heavy Duty Regular Pipe Brace								
				Safe Working Load				
D	w	F	в	Without Knee Bracing	With Knee Bracing			
18'-0"	12'-0"	9'-0"	15'-0"	6,500 lbs.	6,500 lbs.			
19'-0"	12'-8"	9'-6"	15'-10"	6,500 lbs.	6,500 lbs.			
20'-0"	13'-4"	10'-0"	16'-8"	6,500 lbs.	6,500 lbs.			
21'-0"	14'-0"	10'-6"	17'-6"	5,925 lbs.	6,500 lbs.			
22'-0"	14'-8"	11'-0"	18'-4"	4,800 lbs.	6,500 lbs.			
23'-0"	15'-4"	11'-6"	19'-2"	3,925 lbs.	6,500 lbs.			
24'-0"	16'-0"	12'-0"	20'-0"	3,575 lbs.	6,500 lbs.			
25'-0"	16'-8"	12'-6"	20'-10"	2,975 lbs.	6,500 lbs.			
26'-0"	17'-4"	13'-0"	21'-8"	2,500 lbs.	6,500 lbs.			
27'-0"	18'-0"	13'-6"	22'-6"	2,275 lbs.	6,500 lbs.			
28'-0"	18'-8"	14'-0"	23'-4"	1,950 lbs.	6,500 lbs.			

Note: Depending on panel thickness and height, a double mat of reinforcing steel may be required to resist the bending stresses of temporary wind loads.

SWL provides a minimum factor of safety of 1.5 to 1.

Danger! With knee bracing means that knee, lateral and end bracing must be installed in order to obtain SWL's shown.

B-5 Heavy Duty Long Pipe Brace									
				Safe Work	ting Load				
D	w	F	В	Without Knee Bracing	With Knee Bracing				
27'-0"	18'-0"	13'-6"	22'-6"	5,975 lbs.	6,500 lbs.				
28'-0"	18'-8"	14'-0"	23'-4"	5,325 lbs.	6,500 lbs.				
29'-0"	19'-4"	14'-6"	24'-2"	4,800 lbs.	6,500 lbs.				
30'-0"	20'-0"	15'-0"	25'-0"	4,250 lbs.	6,500 lbs.				
31'-0"	20'-8"	15'-6"	25'-10"	3,450 lbs.	6,500 lbs.				
32'-0"	21'-4"	16'-0"	26'-8"	2,825 lbs.	6,500 lbs.				
33'-0"	22'-0"	16'-6"	27'-6"	2,550 lbs.	6,500 lbs.				
34'-0"	22'-8"	17'-0"	28'-4"	2,100 lbs.	6,500 lbs.				
35'-0"	23'-4"	17'-6"	29'-2"	1,750 lbs.	6,500 lbs.				
36'-0"	24'-0"	18'-0"	30'-0"	1,600 lbs.	6,500 lbs.				
37'-0"	24'-8"	18'-6"	30'-10"	1,350 lbs.	6,500 lbs.				
38'-0"	25'-4"	19'-0"	31'-8"	Not Recommended	6,300 lbs.				
39'-0"	26'-0"	19'-6"	32'-6"	Not Recommended	6,000 lbs.				
40'-0"	26'-8"	20'-0"	33'-4"	Not Recommended	5,600 lbs.				
41'-0"	27'-4"	20'-6"	34'-2"	Not Recommended	5,200 lbs.				
42'-0"	28'-0"	21'-0"	35'-0"	Not Recommended	5,000 lbs.				
43'-0"	28'-8"	21'-6"	35'-10"	Not Recommended	4,650 lbs.				
44'-0"	29'-4"	22'-0"	36'-8"	Not Recommended	4,325 lbs.				
45'-0"	30'-0"	22'-6"	37'-6"	Not Recommended	4,175 lbs.				
46'-0"	30'-8"	23'-0"	38'-4"	Not Recommended	3,900 lbs.				
47'-0"	31'-4"	23'-6"	39'-0"	Not Recommended	3,775 lbs.				

Note: Depending on panel thickness and height, a double mat of reinforcing steel may be required to resist the bending stresses of temporary wind loads.

SWL provides a minimum factor of safety of 1.5 to 1.

Danger! With knee bracing means that knee, lateral and end bracing must be installed in order to obtain SWL's shown.

1

# **Table** RS 1000 Push-Pull Prop CB 164 - 224 Adjusting Spindle

#### **RS 1000 Push-Pull Prop** L = 6.40 to 10.00 m Extension length [m] 6.40 7.00 8.00 9.00 10.00 Perm. tension or compr. force N [kN] with symmetrical extension 29.5 26.0 19.6 14.6 11.1 of the inner tubes (K) 6632 5895 Nperm L=6.40 to 10.00 m The chart is taken from the Type Inspection of the State Structural Inspectorate, Düsseldorf (Inspection Certificate P31 - 137/90). It may only be used in conformity with the provisions of this type inspection. The end connections are to take the form of pin joints shown to be structurally adequate α by calculations in each individual case.

## CB 164 - 224 Adjusting Spindle

L = 1.64 to 2.24 m

Ĩ

1

Extension length [m]	1.64	1.80	1.90	2.00	2.10	2.24
Perm. tension or compr. force <b>N</b> [kN] with symmetrical extension of the inner tubes	122.0	109.0	101.0	91.0	80.0	68.0
When used as a compression brace	122.0	98.0	84.0	76.0	72.0	68.0



The chart is taken from the Type Inspection of the State Structural Inspectorate, Düsseldorf (Inspection Certificate P31 - 18/90). It may only be used in conformity with the provisions of this type inspection.

Champlain Towers South - Existing Basement Temporary Wall Bracing Evaluation

The end connections are to take the form of pin joints shown to be structurally adequate by calculations in each individual case

# Wall Formwork

# TableRS and RSS Push-Pull PropsAV Kicker

RS I L = 1.80 to 3.00 m		RS II L = 2.50 to 4.30 m	
Perm. tension/compr. force	= 10 kN	Perm. tension/compr. force	= 8 kN

#### RSS I L = 2.05 to 2.94 m

Extension length [m]	2.05	2.25	2.50	2.75	2.94
Perm. tens./compr. force [kN]	30	30	26	19	16

#### RSS II L = 2.91 to 3.80 m

Extension length [m]	2.91	3.00	3.25	3.50	3.80
Perm. tens./compr. force [kN]	30	30	25	19	13

#### RSS III L = 4.60 to 6.00 m

Extension length [m]	4.60	5.00	5.30	5.65	6.00
Perm. tens./compr. force [kN]	29	24	20	16	12

#### AV Kicker L = 1.08 to 1.40 m Perm. tension/compr. force = 18 kN

#### AV 190 Kicker L = 1.08 to 1.90 m

Extension length [m]	1.08	1.25	1.50	1.75	1.90
Perm. tens./compr. force [kN]	30	30	27	21	18

#### AV Kicker for RSS III L = 2.05 to 2.94 m

Extension length [m]	2.05	2.25	2.50	2.75	2.94
Perm. tens./compr. force [kN]	30	30	26	19	16

#### Table for

#### PERI Push-Pull Props and Kicker Braces

Formwork boight <b>b</b> [m]			pict	ure 1				pict	ure 2
	3.0	4.0	5.0	6.0	7.0	8.0		9.0	10.0
Allowable prop spacing [m]	3.53	2.73	2.19	1.82	1.58	1.42		1.32	1.15
Actual prop load at [kN] maximum prop spacing	9.70	9.70	9.80	9.80	9.80	9.60	F. F.	6.40 6.50	7.80 5.90
Actual kicker load at [kN] maximum prop spacing	2.10	2.30	2.20	2.20	2.30	2.60		1.80	1.60
x = Top connection [m] point from top of formwork	1.00	1.20	1.50	1.80	2.00	2.00	У <sub>1</sub> У <sub>2</sub>	1. <u>5</u> 0 4.50	1.80 5.50
<b>y</b> = Dist. of base plate [m] from front face of formwork	1.15	1.62	2.02	2.42	2.89	3.46	x, x <sub>2</sub>	4.30 2.60	4.73 2.60

Maximum pin force for RSS = 11,3 kN

Resulting wind loads:  $h < 8m = 0.5 \text{ kN/m}^2$ 

 $8m < h < 20m = 0.8 \text{ kN/m}^2$ 

#### Champlain J Ryyers, South The stisting Basement J Remonstration

the area of influence can be altered in the relation of the actual wind load





# Heavy-Duty Spindles SLS and SCS

#### Permissible load-bearing capacity with a symmetrical extension

#### SLS 40/80 L = 0.40 - 0.80 m

Extension Length [m]	0.40-0.80
Perm. Compressive Force [kN]	88.0
Perm. Tension Force [kN]	70.8

#### **SLS 80/140** L = 0.80 - 1.40 m

Extension Length L [m]	0.80-1.40
Perm. Compressive Force [kN]	107.1
Perm. Tension Force [kN]	81.6

#### SLS 100/180 L = 1.00 - 1.80 m

Extension Length L [m]	1.00-1.50	1.60	1.80
Perm. Compressive Force [kN]	107.1	105.5	90.4
Perm, Tension Force [kN]		81.6	

#### SLS 140/240 L = 1.40 - 2.40 m

Extension Length L [m]	1.40	1.50	1.70	1.90	2.00	2.10	2.20	2.30	2.40
Perm. Compressive Force [kN]	138.4	134.7	122.6	109.6	102.5	95.2	87.8	80.5	73.4
Perm. Tension Force [kN]		105.4							

#### SLS 200/300 L = 2.00 - 3.00 m

Extension Length L [m]	2.00	2.20	2.40	2.50	2.60	2.70	2.80	2.90	3.00
Perm. Compressive Force [kN]	136.6	123.6	109.3	101.9	94.4	87.2	79.8	72.9	66.4
Perm. Tension Force [kN]					105.4				

#### SLS 260/360 L = 2.60 - 3.60 m

Extension Length L [m]	2.60	2.80	3.00	3.10	3.20	3.30	3.40	3.50	3.60
Perm. Compressive Force [kN]	133.4	116.2	99.9	91.9	84.3	77.3	70.6	64.6	59.0
Perm. Tension Force [kN]		0	14.		105.4				

#### SLS 320/420 L = 3.20 - 4.20 m

Extension Length L [m]	3.20	3.40	3.50	3.60	3.70	3.80	3.90	4.00	4.10	4.20	
Perm. Compressive Force [kN]	117.1	101.2	92.8	85.5	78.6	72.1	66.1	60.2	55.8	51.2	
Perm. Tension Force [kN]		105.4									

#### SLS 380/480 L = 3.80 - 4.80 m

Extension Length L [m]	3.80	3.90	4.00	4.10	4.20	4.30	4.40	4.50	4.60	4.70	4.80
Perm. Compressive Force [kN]	85.5	80.6	76.1	71.8	67.6	63.7	59.9	55.4	51.3	47.5	43.9
Perm. Tension Force [kN]		105.4									

#### SCS 198/250 L = 1.98 - 2.50 m

Extension Length L [m]	1.98	2.10	2.20	2.30	2.40	2.50
Perm. Compressive Force [kN]	264	247	233	217	197	175
Perm. Tension Force [kN]			2	11		

# Additional information for SLS Spindles:

When using the SLS Spindle with Pin Ø 21 x 120 (Item no. 104031) or Hex. Bolt M20x100-8.8 on the SRU Steel Waler, a maximum load of 70 kN applies.

- values according to Type Test S-N-050528!
- horizontal to vertical applications.
- dead load and wind load on the props considered.
- intermediate values are to be linearly interpolated.
- bearing stress and bolt bending of the connection are to be verified separately.

#### Additional information for SCS Spindles:

- values according to Type Test!
- horizontal to vertical applications.
- dead load and wind load on the props considered.
- intermediate values are to be linearly interpolated.
- bearing stress and bolt bending of the connection are to be verified separately.

4.058m

Nominal Bolt Diameter, d, in.

Nominal Bolt Area, in.2

Thread

Cond.

Ν

х

Ν

х

-

Thread

Cond.

Ν

х

Ν

Х

-

LRFD

¢ = 0.75

 $F_{mv}/\Omega$ φFm

(ksi) (ksi)

ASD LRFD

27.0 40.5

34.0 51.0

34.0 51.0

42.0 63.0

13.5 20.3

 $F_{nv}/\Omega$ ¢Fnv

(ksi) (ksi)

ASD LRFD

27.0 40.5

34.0 51.0

34.0 51.0

42.0 63.0

13.5

20.3

Nominal Bolt Diameter, d, in.

Nominal Bolt Area, in.<sup>2</sup>

Champlain Towers South - Existing Basement Temporary Wall Bracing Evaluation

ASTM

Desig.

Group

A

Group

В

A307

ASTM

Desig.

Group

A

Group

В

A307

ASD

 $\Omega = 2.00$ 

#### DESIGN CONSIDERATIONS FOR BOLTS

7/8

0.601

LRFD ASD LRFD

24.3

48.7

12.2

24.4

75.5 60.2 90.3

151

1

0.785

 $r_n |\Omega|$ 04

21.2 31.8

42.4

267

63.5

80.1

40.0

80,1

49.5

98.9

15.9

11/2

1.77

rn/Q Oth

ASD LRFD

95.6 143

74.3

Table 7-1 **Available Shear** Strength of Bolts, kips

5/8

0.307

12.4

15.7

31.3

15.7

 $r_n/\Omega$ ¢ľn  $r_n/\Omega$ φr<sub>n</sub>  $r_n/\Omega$ φr<sub>a</sub>

ASD LRFD

8.29

16.6 24.9 23.9 35.8 32.5

10.4

10.4

20.9 31.3 30.1 45.1

12.9 19.3 18,6 27.8 25.2 37.9

25.8 38.7

 $r_n/\Omega$  $\phi r_n$ 

ASD LRFD ASD LRFD ASD LRFD

26.8 40.3 33.2

33.8 50.7 41.8 62.7 50.3

67.6

41.7

13.4 20.2 16.6 25.0 20.0 30.0 23.9

26.8

101

125

62.6

40.4

4.14 6.23

8.29 12.5

11/8

0.994

Load-

ing

S

D

S

D

S

D

S

D

S

Load-

ing

S

D 53.7 80.5 66.4

S

D 67.6 101

S 33.8 50.7 41.8 62.7 50.3 75.5 60.2 90.3

D

S

D

S

D

3/4

0.442

ASD

11.9

15.0

30,1 15.0

37.1 55.7 50.5 75.7

5.97 8.97 17.9

11.9

 $r_n/\Omega$ φ**r**<sub>n</sub>  $r_n/\Omega$ ¢r<sub>n</sub>

83.6 125

83.6 125 101 151

103 155 124 186

33.2 For end loaded connections greater than 38 in., see AISC Specification Table J3.2 footnote b

11/4

1.23

49.8 40.0 59.9 47.8

99.6 79.9 120

77.5

49.9

62.2 93.2

40.0 60.1

LRFD ASD

17.9

22.5

45.1 40.9 61.3

22.5 20.4 30.7

16.2

20,4 30.7 26.7 40.0

40.9 61.3

8.11

16.2

13/8

1.48

DESIGN TABLES

 $\Omega = 2.00$   $\phi = 0.75$ 

	•	Stre	Avai engt	Tabl labl h of	e 7-2 e Te Bo	nsil Its,	e kips			
Nominal Bolt	Diameter,	d, in.	5	/8	<sup>3</sup> /4 0.442		1	/8		1
Nominal Bo	olt Area, ir	L <sup>2</sup>	0.	307			0.601		0.75	
ISTM Desig.	F <sub>nt</sub> /Ω (ksi)	φ <i>F<sub>nt</sub></i> (ksi)	<b>r</b> <sub>n</sub> /Ω	φ <b>r</b> n	r <sub>n</sub> /Ω	φ <b>r</b> <sub>n</sub>	r <sub>a</sub> /Ω	¢r <sub>n</sub>	r <sub>n</sub> /Ω	Γ
	ASD	LRFD	ASD	LRFD	ASD	LRFD	ASD	LRFD	ASD	
Group A	45.0	67.5	13.8	20.7	10.0	20.9	27.1	10.0		

7-23

ASTM Desig.	F <sub>nt</sub> /Ω (ksi)	φ <i>F<sub>nt</sub></i> (ksi)	$r_n/\Omega$	φ <b>r</b> <sub>n</sub>	r <sub>n</sub> /Ω	φ <b>r</b> <sub>n</sub>	$r_n/\Omega$	¢r <sub>n</sub>	r <sub>n</sub> /Ω	φ <b>r</b> <sub>n</sub>
	ASD	LRFD	ASD	LRFD	ASD	LRFD	ASD	LRFD	ASD	IRED
Group A Group B A307	45.0 56.5 22.5	67.5 84.8 33.8	13.8 17.3 6.90	20.7 26.0 10.4	19.9 25.0 9.94	29.8 37.4 14.9	27.1 34.0 13.5	40.6 51.0 20.3	35.3 44.4 17.7	53.0 66.6 26.5
Nominal Bolt Diameter, d, in.			1	1/8	1	1/4	1	3/8	1 <sup>1</sup> / <sub>2</sub>	
Nominal Bolt Area, in. <sup>2</sup>			0.9	994	1	.23	1	48		
ASTM Desig.	F <sub>nt</sub> /Ω (ksi)	¢F <sub>nt</sub> (ksi)	$r_n/\Omega$	φr <sub>n</sub>	$r_{a}/\Omega$	¢r <sub>n</sub>	$r_n/\Omega$	¢r <sub>n</sub>	r <sub>a</sub> /Ω	¢r <sub>n</sub>
	ASD	LRFD	ASD	LRFD	ASD	LRFD	ASD	LRFD	ASD	LRED
Group A Group B A307	45.0 56.5 22.5	67.5 84.8 33.8	44.7 56.2 22.4	67.1 84.2 33.5	55.2 69.3 27.6	82.8 104 41.4	66.8 83.9 33.4	100 126	79.5 99.8	119 150
ASD	LRFD					11.4	00.4	50.1	33.0	9,60

#### HIT-HY 200 Adhesive Anchoring System

Table 1 — HIT-HY 200 Design Strength (Factored Resistance) with Concrete/Pullout Failure for HIT-Z(-R) Rods in Uncracked Concrete 1:2:3:4:5:6:7:8:10

	Effective Embed. Depth in. (mm)		Tension -	-ΦN <sub>n</sub> or N <sub>r</sub>		Shear — $\Phi V_a$ or $V_r$			
Anchor Diameter in. (mm)		f' <sub>c</sub> = 2500 psi (17.2 Mpa) Ib (kN)	f <sup>*</sup> <sub>c</sub> = 3000 psi (20.7 Mpa) Ib (kN)	f <sub>c</sub> = 4000 psi (27.6 Mpa) Ib (kN)	f' <sub>c</sub> = 6000 psi (41.4 Mpa) Ib (kN)	f <sub>c</sub> = 2500 psi (17.2 Mpa) Ib (kN)	f <sub>c</sub> = 3000 psi (20.7 Mpa) Ib (kN)	f' <sub>c</sub> = 4000 psi (27.6 Mpa) Ib (kN)	f'_c = 6000 psi (41.4 Mpa) Ib (kN)
3/8 (9.5)	2-3/8 (60) 3-3/8 (86)	2,855 (12.7) 4,835 (21.5)	3,125 (13.9) 5,300 (23.6)	3,610 (16.1) 5,560 (24.7)	4,425 (19.7) 5,560 (24.7)	3,075 (13.7) 10,415 (46.3)	3,370 (15.0) 11,410 (50.8)	3,890 (17.3) 13,175 (58.6)	4,765 (21.2) 16,135 (71.8)
	4-1/2 (114)	5,560 (24.7)	5,560 (24.7)	5,560 (24.7)	5,560 (24.7)	16,035 (71.3)	17,570 (78.2)	20,285 (90.2)	24,845 (110.5)
1/2 (12.7)	2-3/4 (70) 4-1/2 (114) 6	3,555 (15.8) 7,445 (33.1) 8,190	3,895 (17.3) 8,155 (36.3) 8,190	4,500 (20.0) 8,190 (36.4) 8,190	5,510 (24.5) 8,190 (36.4) 8,190	7,660 (34.1) 16,035 (71.3) 24,690	8,395 (37.3) 17,570 (78.2) 27,045	9,690 (43.1) 20,285 (90.2) 31,230	11,870 (52.8) 24,845 (110.5) 38,250
	(152) 3-3/4	(36.4) 5,665	(36.4) 6,205	(36.4) 7,165	(36.4) 8,775	(109.8) 12,200	(120.3) 13,365	(138.9) 15,430	(170.1) 18,900
5/8 (15.9)	(95) 5-5/8 (143) 7-1/2	(25.2) 10,405 (46.3) 14,950	(27.6) 11,400 (50.7) 14,950	(31.9) 13,165 (58.6) 14,950	(39.0) 14,950 (66.5) 14,950	(54.3) 22,415 (99.7) 34,505	(59.5) 24,550 (109.2) 37,800	(68.6) 28,350 (126.1) 43,650	(84.1) 34,720 (154.4) 53,455
3/4 (19.1)	(191) 4 (102) 6-3/4	(66.5) 6,240 (27.8) 13,680	(66.5) 6,835 (30.4) 14,985	(66.5) 7,895 (35.1) 17,305	(66.5) 9,665 (43.0) 19,890	(153.5) 13,440 (59.8) 29,460	(168.1) 14,725 (65.5) 32,275	(194.2) 17,000 (75.6) 37,265	(237.8) 20,820 (92.6) 45,645
	(171) 8-1/2 (216)	(60.9) 19,330 (86.0)	(66.7) 19,890 (88.5)	(77.0) 19,890 (88.5)	(88.5) 19,890 (88.5)	(131.0) 41,635 (185.2)	(143.6) 45,605 (202.9)	(165.8) 52,660 (234.2)	(203.0) 64,500 (286.9)

Table 2 — HIT-HY 200 Design Strength (Factored Resistance) with Concrete/Pullout Failure for HIT-Z(-R) Rods in Cracked Concrete 1.2,3,4,5,8,7,8,9,10

	Effective		Tension -	- ΦN, or N,		Shear — $\Phi V_n$ or $V_r$			
Anchor	Embed.	f' = 2500 psi	f' = 3000 psi	f' = 4000 psi	f' = 6000 psi	f = 2500 psi	f' = 3000 psi	f' = 4000 psi	f' = 6000 psi
Diameter	Depth	(17.2 Mpa)	(20.7 Mpa)	(27.6 Mpa)	(41.4 Mpa)	(17.2 Mpa)	(20.7 Mpa)	(27.6 Mpa)	(41.4 Mpa)
in. (mm)	in. (mm)	lb (kN)	Ib (kN)	Ib (kN)	lb (kN)	lb (kN)	lb (kN)	lb (kN)	Ib (kN)
	2-3/8	2,020	2,215	2,560	3,135	2,180	2,385	2,755	3,375
	(60)	(9.0)	(9.9)	(11.4)	(13.9)	(9.7)	(10.6)	(12.3)	(15.0)
3/8	3-3/8	3,425	3,755	4,335	5,305	7,380	8,085	9,335	11,430
(9.5)	(86)	(15.2)	(16.7)	(19.3)	(23.6)	(32.8)	(36.0)	(41.5)	(50.8)
	4-1/2	5,275	5,560	5,560	5,560	11,360	12,445	14,370	17,600
	(114)	(23.5)	(24.7)	(24.7)	(24.7)	(50.5)	(55.4)	(63.9)	(78.3)
	2-3/4	2,520	2,760	3,185	3,905	5,425	5,945	6,865	8,405
	(70)	(11.2)	(12.3)	(14.2)	(17.4)	(24.1)	(26.4)	(30.5)	(37.4)
1/2	4-1/2	5,275	5,780	6,670	7,640	11,360	12,445	14,370	17,600
(12.7)	(114)	(23.5)	(25.7)	(29.7)	(34.0)	(50.5)	(55.4)	(63.9)	(78.3)
	6	7,640	7,640	7,640	7,640	17,490	19,160	22,120	27,095
	(152)	(34.0)	(34.0)	(34.0)	(34.0)	(77.8)	(85.2)	(98.4)	(120.5)
	3-3/4	4,010	4,395	5,075	6,215	8,640	9,465	10,930	13,390
	(95)	(17.8)	(19.5)	(22.6)	(27.6)	(38.4)	(42.1)	(48.6)	(59.6)
5/8	5-5/8	7,370	8,075	9,325	11,420	15,875	17,390	20,080	24,595
(15.9)	(143)	(32.8)	(35.9)	(41.5)	(50.8)	(70.6)	(77.4)	(89.3)	(109.4)
	7-1/2	11,350	12,430	14,355	14,950	24,440	26,775	30,915	37,865
	(191)	(50.5)	(55.3)	(63.9)	(66.5)	(108.7)	(119.1)	(137.5)	(168.4)
	4	4,420	4,840	5,590	6,845	9,520	10,430	12,040	14,750
	(102)	(19.7)	(21.5)	(24.9)	(30.4)	(42.3)	(46.4)	(53.6)	(65.6)
3/4	6-3/4	9,690	10,615	12,255	15,010	20,870	22,860	26,395	32,330
(19.1)	(171)	(43.1)	(47.2)	(54.5)	(66.8)	(92.8)	(101.7)	(117.4)	(143.8)
	8-1/2	13,690	15,000	17,320	19,535	29,490	32,305	37,300	45,685
	(216)	(60.9)	(66 7)	(77.0)	(86.9)	(131.2)	(143 7)	(165.9)	(203.2)

1 See Section 2.4 for explanation on development of load values.

2 See Section 2.4.6 to convert design strength (factored resistance) value to ASD value.

3

Linear interpolation between embedment depths and concrete compressive strengths is not permitted. Apply spacing, edge distance, and concrete thickness factors in tables 8 - 15 as necessary. Compare to the steel values in table 3. The lesser of the values is to be used for the design. 4 5

Apply spacing, edge distance, and concrete thickness factors in tables 3 - 10 as necessary. Compare to the steer values in table 3. The lesser of the values is to be used for the design. Data is for temperature range A: Max, short term temperature =  $176^{\circ}$  F ( $40^{\circ}$  C), max, long term temperature =  $122^{\circ}$  F ( $24^{\circ}$  C). For temperature range B: Max, short term temperature =  $176^{\circ}$  F ( $40^{\circ}$  C), max, long term temperature =  $122^{\circ}$  F ( $50^{\circ}$  C) multiply above value by 0.86. For temperature range C: Max, short term temperature =  $248^{\circ}$  F ( $120^{\circ}$  C), max, long term temperature =  $162^{\circ}$  F ( $72^{\circ}$  C) multiply above value by 0.70. Short term elevated concrete temperatures are those that occur over brief intervals, e.g., as a result of diurnal cycling. Long term concrete temperatures are roughly constant over significant periods of time.

6 Tabular values are for dry and water saturated concrete conditions.

Tabular values are for short term loads only. For sustained loads, see Section 2.4.8.

Tabular values are for normal weight concrete only. For lightweight concrete multiply design strength (factored resistance) by  $\lambda_s$  as follows: 8

For sand-lightweight,  $\lambda_a = 0.51$ . For all-lightweight,  $\lambda_a = 0.45$ .

9 Tabular values are for static loads only. For seismic loads, multiply cracked concrete tabular values by the following reduction factors:

3/8-in diameter -  $\alpha_{sel} = 0.705$ 1/2-in to 3/4-in diameter -  $\alpha_{sel} = 0.75$ See Section 2.4.7 for additional information on seismic applications.

10 Diamond core drilling with Hilti HIT-Z(-R) rods is permitted with no reduction in published data above.

### HIT-HY 200 Adhesive Anchoring System

The full shear strength can be permitted if:

ACI: 
$$\frac{N_{ua}}{N_{des}} \le 0.2$$

CSA: 
$$\frac{N_r}{N_{des}} \le 0.2$$

#### 2.4.6 Allowable Stress Design (ASD)

The values of  $N_{des}$  and  $V_{des}$  developed from Section 2.4.5 are design strengths (factored resistances) and are to be compared to the required strength in tension and shear from factored load combinations of ACI 318 Chapter 9 or CSA A23.3 Chapter 8.

The design strength (factored resistance) can be converted to an ASD value as follows:

$$N_{des,ASD} = \frac{N_{des}}{\alpha_{ASD}}$$
$$V_{des,ASD} = \frac{V_{des}}{\alpha_{ASD}}$$

where:

 $\alpha_{ASD}$  = Conversion factor calculated as a weighted average of the load factors for the controlling load combination.

An example for the calculation of  $\alpha_{ASD}$  is as follows:

Controlling strength design load combination is 1.2D + 1.6L, % contribution is 30% D, 70% L

$$\alpha_{ASD} = 1.2 \times 0.30 + 1.6 \times 0.70 = 1.48$$

#### 2.4.7 Seismic Design

To determine the seismic design strength (factored resistance) a reduction factor,  $\alpha_{seis}$ , is applied to the applicable table values. This value of  $\alpha_{seis}$  will be in the footnotes of the relevant design tables.

The value of  $\alpha_{sels}$  for concrete / bond / pullout failure is based on 0.75 times a reduction factor determined from testing. The total reduction is footnoted in the tables.

The value of  $\alpha_{sels}$  for steel failure is based on testing and is typically only applied for shear. There is no additional 0.75 factor. The reduction is footnoted in the tables.

The factored load and associated seismic load combinations that will be compared to the design strength (factored resistance) can be determined from ACI or CSA provisions and national or local code requirements. An additional value for  $\phi_{non-ductile}$  may be needed based on failure mode or ductility of the attached components.

#### 2.4.8 Sustained Loads and Overhead Use

Sustained loading is calculated by multiplying the value of  $\Phi N_n$  or  $N_r$  by 0.55 and comparing the value to the tension dead load contribution (and any sustained live loads or other loads) of the factored load. Edge, spacing, and concrete thickness influences do not need to be accounted for when evaluating sustained loads.

Consideration of sustained loads is based on ACI 318-11 Appendix D. Since sustained loading is not addressed in CSA A23.3 Annex D, it is reasonable to use this approach for CSA based designs.

#### 2.4.9 Accuracy of the Simplified Tables

Calculations using the Simplified Tables have the potential of providing a design strength (factored resistance) that is exactly what would be calculated using equations from ACI 318 Appendix D or CSA A23.3 Annex D.

The tables for the single anchor design strength (factored resistance) for concrete / bond / pullout failure or steel failure have the same values that will be computed using the provisions of ACI and CSA.

The load adjustment factors for edge distance influences are based on a single anchor near an edge. The load adjustment factors for spacing are determined from the influence of two adjacent anchors. Each reduction factor is calculated for the minimum value of either concrete or bond failure. When more than one edge distance and/or spacing condition exists, the load adjustment factors are multiplied together. This will result in a conservative design when compared to a full calculation based on ACI or CSA. Additionally, if the failure mode in the single anchor tables is controlled by concrete failure, and the reduction factor is controlled by bond failure, this will also give a conservative value (and vice versa).

The following is a general summary of the accuracy of the simplified tables:

- Single anchor tables have values equivalent to a calculation according to ACI or CSA.
- Since the table values, including load adjustment factors, are calculated using equations that are not linear, linear interpolation is not permitted. Use the smaller of the two table values listed. This provides a conservative value if the application falls between concrete compressive strengths, embedment depths, or spacing, edge distance, and concrete thickness.
- For one anchor near one edge, applying the edge distance factor typically provides accurate values

# EXHIBIT "B"



Site Specific Safety Plan

For Construction of steel braces for concrete retaining wall all around the property to provide structural support for the existing concrete retaining wall

Subject Property:

8777 Collins Ave., Surfside, FL, 33154

TO: BOFMAN CONSTRUCTION CO

PREPARED BY CALC ENGINEERING LLC

8/5/2021



# Site Specific Safety Plan

For Construction of steel braces for concrete retaining wall all around the property to provide structural support for the existing concrete retaining wall

Subject Property:

8777 Collins Ave., Surfside, FL, 33154

# TABLE OF CONTENTS

ntroduction	3
Company Policy	4
Contractor Responsibilities	5
Background and Scope of Work	6
Safety and Emergency Contacts	7
Safety Hazards on Job Site and Considerations	8
Pictures	11
Common Safety Procedures	34
Construction Signage	38



Site Specific Safety Plan

# For Construction of steel braces for concrete retaining wall all around the property to provide structural support for the existing concrete retaining wall.

Address: 8777 Collins Ave., Surfside, FL, 33154

# Introduction

The subject property, the collapsed site of the Champlain towers at Surfside, Florida, was visited on Sunday 08/01/2021 and on Thursday 8/5/2021 by Calc Engineering LLC team. Calc Engineering performed visual inspection of walls in order to provide site specific safety plan for the damages and structural issues on remaining concrete walls around the perimeter of the collapsed building before installation of the new steel bracing system.

The Contractor shall have sole and complete responsibility for the implementation of a worksite safety plan and shall take necessary precautions for the health and safety of employees and fully comply with applicable provisions of all sections of 29 CFR 1926-OSHA Construction Industry Safety and Health Standards, 29 CFR 1910-OSHA General Industry Safety and Health Standards, National Fire Protection Association codes, and all standards or codes referred to in the listed document and any other applicable standards.

Due to the changing nature of health and safety regulations, and because new information is constantly becoming available, this plan is subject to change.



# **Company Policy**

Safety and health of the workforce and general public is the top priority of Calc Engineering. In case of potential safety or health threat, all efforts will be made to minimize or eliminate hazards to personnel, processes, equipment, and the general public. No worker should ever perform a task that may endanger their own safety and health or that of others. All workers must report unsafe activities and potential threats to management and management must take adequate precautions.

This SSSP outlines the Environment, Safety, and Health (ES&H) requirements and guidelines developed for construction of steel braces for concrete retaining wall all around the property to provide more structural support for existing concrete retaining wall. These requirements are written to help protect site personnel, visitors, and the general public from exposure to potential hazards on this job site. There are several plans and actions that are included to ensure that we act to protect the environment, the general public, as well as the workforce during the construction phase of this project. This plan shall be updated if there are major changes to project conditions, situations, or exposures. An employee acknowledgement form documents that each employee understands the SSSP and will implement these safety and health requirements on this job site.



# **Contractor Responsibilities**

The contractor, BOFAM Construction Co. must perform safety inspections of their work area and equipment per OSHA requirements, and plan for the safety of the job site by

- 1- Making periodic inspections and confirm the job site safety
- 2- Enforce the use of safety equipment and PPE
- 3- Hold daily meetings to inspect the job site and equipment safety
- 4- Discuss the hazards with all necessary parties
- 5- Provide recommendations and address all safety concerns
- 6- Eliminate potential threats and possibility of accidents and injuries
- 7- Provide safety orientations and enforce safety rules

All employees must receive a project safety assignment to the project. Topics include but not limited to, Fall Protection, ladder Safety, hazard Communication, lock out/tag out. All employees must complete the contractor's safety orientation and sign the necessary forms. The training records to be maintained electronically and/or on site in the job site office. Should OSHA visit the job site, these training records are one indication of our implementation of an active safety program on this site. Safety meetings to be scheduled to review safety inspections, findings, and corrective actions taken. The project manager should schedule routine meetings in advance or set a regular date/time to be sure that all workers can plan to attend this safety meeting. Records of these meetings should be kept on file in the job site office with attached attendance sheets.



For all observed hazards and provided recommendations, reports must be maintained and submitted to Calc Engineering. If contractor believes there will be delay due to impact of harsh weather conditions, or when the project site is determined to be unworkable, the engineers and site manager shall meet to assess the conditions of construction site. All incidents to be discussed at safety meetings to eliminate the recurrence of such incidents in future. It is the contractor's duty to administer all the common safety procedures and address/manage the safety hazards mentioned in this report.

Contractor shall report all work related injuries, illnesses, first aid cases, near misses, property damage, and environmental incidents such as a spill or release of hazardous materials, regardless of severity, immediately to the Project Superintendent. Contractor shall investigate all incidents and forward copies of the incident report to the Project Superintendent within 4 hours of the incident. An incident report must be provided for: near misses, first aid, recordable injuries, third party property damage or personal injury.

# **Background and Scope of Work**

The subject property, the collapsed site of the Champlain towers at Surfside, Florida, was visited on Sunday 08/01/2021 and on Thursday 8/5/2021 by Calc Engineering LLC team. Calc Engineering performed visual inspection of walls in order to provide site specific safety plan for the damages and structural issues on remaining concrete walls around the perimeter of the collapsed building before installation of the new steel bracing system.

Visual inspections were made of the above described property and photographs were taken for review, and some recommendations were provided to enhance the safety of the workforce against failure of the remaining parts of columns and retaining walls. Calc Engineering cannot say or evaluate those sections that was not visible. Calc engineering only inspected the retaining walls and did not inspect other



sections. Calc Engineering believes that after the site is drained completely, the area around the remaining columns needs to be secured, the remaining rebars need to be cut. The hanging concrete parts must be removed. The remaining of the 7' privacy concrete wall need to be completely removed or secured. The ramp access must be extended for safe travel of construction equipment. All the exposed rebars on the concrete floor need to be cut.

Our recommendation in this report is proper and applicable for the time of inspection, and not for future. It is our purpose to provide information on the condition of the structure on the day of the inspection and not to provide discussions or recommendations concerning the future maintenance of the structure.

Contacts					
Project Manager	Austin G. Akinrin (BOFAM Construction Co.)				
Site Name	Champlain Towers				
Site Address	8777 Collins Ave., Surfside, FL 33154				
Local Police, Ambulance, and Fire Dept.	911				
Local Hamital: Mount Sinai Madical Contar	Tel: (305) 674-2200 and (305) 396-3219				
Local Hospital. Mount Sinal Medical Center	Address: 4300 Alton Road, Miami Beach, FL 33140				
Local Contractor's Office	1600 NW 3 <sup>rd</sup> Ave, Suite D4, Miami, FL 33136				
Local Contractor's Onice	Tel: (754) 245-0102				

## Safety and Emergency Contacts





Direction to closest Hospital:

# Safety Hazards on Job Site and Considerations

- At all times during the construction, the area of the work must be dry. After the area is completely dry, contractor needs to confirm there are no slippery areas on the concrete floor before and during the construction period (Figure 1).
- 2. There are concrete columns in middle of the site with exposed rebars that are structurally unsafe and unsecured. The columns are detached and may collapse, Calc Engineering recommends removing or securing all columns to avoid any incidents (Figure 2).



- 3. There's a 7' high privacy concrete wall unbraced and unsecured on side of the 87<sup>th</sup> terrace around the pool area. Multiple large cracks are visible on the structure. Calc Engineering recommends that concrete privacy wall to be removed or engineering plans required to secure the wall. The wall is not safe during hurricane event and may collapse (Figure 3).
- Ramp access for the construction equipment is not wide enough for travel of construction equipment and is not secured from one side, contractor to extend the width of the ramp or temporary pile sheets to be included in that area (Figure 4).
- Concrete beams and columns around pool are all damaged. The columns are damaged, with large cracks visible on the structure, the concrete slab is unreinforced and damaged, the pool area is extremely unsafe and must be secured or completely demolished before construction of bracing systems starts. (Figure 5).
- 6. Rebars hanging from all around of the existing concrete walls to be cut before the construction starts (Figure 6).
- 7. All hanging broken concrete pieces and debris must be removed before the start of construction of the steel bracing system (Figure 7).
- The remaining floor/slab on corner of 88 St and the ocean side is unsafe (Northeast corner of the site) needs to be removed or secured (Figure 8) before construction of bracing systems starts.
- 9. All rebars on the concrete floor to be removed or secured to prevent any incident during the construction (Figure 9).
- 10. The debris and remaining rubble on top of all walls need to be removed, may fall during the construction.

Calc Engineering recommends demolishing or securing the hazard areas mentioned (Pool area, concrete wall around pool area, the concrete floor on Northeast corner on side of 88 St., all remaining columns, all remaining exposed hanging rebars and broken/damaged concrete pieces and remaining rebars on concrete floor).



All damages on the surface of the concrete wall must be repaired before the construction starts. The structural plans provided by Calc Engineering are temporary and for duration of six months. The condition of steel plate and bracings need to be checked after 6 months.

Since the bracing design is with assumption of having the first lane and walkway of Collins Ave. closed; in case they are opened or any extra load is applied, the structural and safety plans need to be checked.

As mentioned in project prioritization section, the first priority for the construction is the wall on the side of Collins Ave., second priority is the side of 88th St and third is the size of 87 terrace and last is the ocean side.

The figures below display some of the hazards mentioned above.



**Pictures** 



Figure 1: The area must be fully drained





Fig 2(a): view of columns with exposed rebars





Fig 2(b): detached and damaged columns





Fig 2(c) damaged columns with exposed rebars present threat to workers safety. Figure 2: Columns with exposed rebars to be secured or removed.





Fig 3(a) unbraced and unsafe damaged concrete wall





Fig 3(b): cracks visible on the unbraced wall





Fig 3(c) cracks on the unbraced concrete wall

Figure 3: Unbraced 7' concrete wall on side of 87<sup>th</sup> Terrace around pool area, large cracks visible (the wall is unbraced and unsecure, may collapse during hurricane).





Figure 4: Ramp not wide enough needs to be extended for travelling of future heavy construction equipment.





Figure 5 (a): Pool area must be secured.





Fig 5 (b) Column detached, beam cracked, broken concrete hanging





Fig 5 (c) Cracks under the pool area





Fig 5 (d) Hanging rebars and broken concrete, separation of concrete slab.





Fig 5(e) Concrete slab is unreinforced and damaged, may collapse

Figure 5: Damaged area under pool. Cracks and spalling, concrete separation and cracks, hanging rebars and broken concrete.





Fig 6 (a) Hanging rebars on side of 87<sup>th</sup> Terrace




Fig 6 (b) Hanging rebars on side of Collins Ave.





Fig 6 (c) Hanging rebars on side of Collins Ave.



Fig 6 (d) Hanging rebars on side of 88 street.





Fig 6(e) Hanging rebars on ocean/east side.

Figure 6: Hanging rebars on all concrete walls to be removed.





Fig 7 (a) Broken concrete on side on 87<sup>th</sup> Terrace





Fig 7 (b) Broken concrete on side on 87<sup>th</sup> Terrace





Fig 7 (c) Broken concrete on side of Collins Ave.



Fig 7 (d) Broken concrete on side of Colins Ave.





Fig 7(e) Broken concrete on side of Collins Ave.





Fig 7(f) Broken concrete to be removed on the ocean/east side.



Fig 7(g) Broken concrete to be removed on the ocean/east side.

Figure 7: Damaged/broken concrete pieces to be removed on all walls.





Figure 8: East corner of 88 St. to be secured or the slab to be removed.



Figure 9: Rebars to be removed from concrete floor



# **Common Safety Procedures**

The contractor is required to follow general safety and health provisions as required by OSHA. It is contractors' responsibility to provide safety training and education, provide first aid and medical attention, prepare ventilation systems when required, provide fire extinguishers, properly dispose of debris and hazardous materials, and record and report the injuries.

### Hazard Communication Standard- 29CFR 1910.1200

1. A list of hazardous substances must be available for all employees.

2. Proper training is required for work force to identify the location of hazards, MSDS safety data sheet, protective measures to be taken, and details of hazard communication program.

3. Employees must be aware of all potential hazards and be trained for handling the hazardous materials used in the workplace.

4. All employees must use personal protective equipment.

5. Proper control procedures are to be established for handling of hazardous materials.

#### Housekeeping- 29 CFR 1910.22 and/or 29 CFR 1926.25

1. All work surfaces must be kept clean, dry and slip resistant.

2. Any spill of hazardous materials, liquid, blood, and infectious materials must be cleaned up properly immediately.

3. Debris and waste must be removed from the worksite properly .

#### Hand and Power Tools- 29 CFR 1926 Subpart I or 29 CFR 1910 Subpart P

1. All equipment must be provided with appropriate safety guards.

2. Power tools shall be used with proper shields, guards, or attachments, as recommended by the manufacturer.

3. Electrically operated tools and equipment must be grounded.

4. All tools and equipment must be kept in good condition.

#### Mechanized Equipment- 29 CFR 1926 Subpart O

1. Employees must be trained or be licensed to operate any mechanized equipment.

2. Does the mechanized equipment have a warning horn, whistle, gong, or other device that can be clearly heard above normal noise in the areas where it is operated.

3. If any equipment requires repairs, it should be removed from worksite immediately.

#### Trenching and Shoring- 29 CFR 1926 Subpart P

1. The safety representative must be present at all times on site.



2. Workers must be protected from cave-ins in all demolition parts by an adequately designed protective system.

3. Work must be done only in areas protected by sloping and benching, a support system, or a shield system.

4. Material and equipment used for protective systems must be the right size and in good condition.

5. The safety inspector checks the site (a) every day before work, (b) after every rainstorm, and (c) as needed, for evidence of possible cave-ins, failure of systems, hazardous atmospheres.

# Traffic Control- 29 CFR 1926 Subpart G

1. All passageways must be kept clear and arranged such that the employees operating machineries are kept safe at all times.

2. Exposed rebars, holes and defects in the floor, sidewalk and all walking surfaces must be kept covered and secured.

3. Spilled material must be cleaned immediately.

### Fall Protection- 29 CFR 1926 Subpart M and/or 29 CFR 1926 Subpart X

1. Ladders must be kept in good condition, joints between steps and side rails kept tight, all hardware and fittings must be securely attached, and moveable parts should operate freely. Employees are prohibited from using ladders that are broken, missing side rail, and are in any way defective.

2. non-slip safety feet must be provided on each metal or rung ladder. All ladders must be free of grease and oil.

3. All ladders must be inspected for damages.

4. Floor openings must be guarded and secured.

#### PPE- 29 CFR 1910 Subpart I

1. All employees must wear proper PPE for head, eye, face, hand, and foot protection. Employees must be trained on PPE use procedure, which PPE is required, when to use them and how to properly adjust them.

2. Due to the hazards identified, all employees must wear protective gloves, hard hats, safety glasses, foot protection and safety vest.

#### Lock-out/ Tag-out- 29 CFR 1910.147

1. All machinery are required to be de-energized or disengaged and blocked or locked out during cleaning, servicing, and adjusting. Ensure control circuit is disconnected and locked out for electrical equipment.



2. The stored energy (mechanical, hydraulic, air, etc.) must be released or blocked before equipment is locked out for repairs.

3. Employees working on locked-out equipment have to be identified (by their locks or accompanying tags).

# Hot Work- 29 CFR 1910 Subpart Q

1. Only authorized and trained personnel are permitted to use welding, cutting, or brazing equipment.

2. Signs to be posted reading "DANGER, NO SMOKING, MATCHES, OR OPEN LIGHTS," or the equivalent.

3. Safety glasses required to be worn at all times in areas where there is a risk of eye injuries such as punctures, abrasions, contusions, or burns.

4. Verify that the eye protection, helmets, hand shields and goggles meet appropriate standards.

5. Adequate ventilation required where welding or cutting is performed.

6. Fire extinguishing equipment must be made available in the worksite.

# Environmental- 29 CFR 1910 Subpart J

1. Use wet methods and air intakes to eliminate the risk of contaminated air, dust or similar hazards.

2. Employees must be made aware of the hazards involved with the various chemicals they may be exposed to in their work environment, such as ammonia, chlorine, epoxies, caustics.

# Occupational Health- 29 CFR 1910 Subpart K

1. Employees are prohibited from smoking or eating in any area where contaminants are present.

2. First aid kits supplied in each work area and periodically being inspected.

3. Emergency phone numbers to be posted.

4. Prepare an eye-wash station or sink for quick drenching or flushing of the eyes and body in areas where corrosive liquids or materials are handled.

# Removal of Bonded Asbestos Containing Materials (ACM)

1. Asbestos Containing Material (ACM) means any material, object, product or debris that contains asbestos.



- 2. ACM related work means any work that involves working on (drilling, cutting, scraping, cleaning, repairing etc), removing or working in close proximity to, installed ACM.
- 3. Bonded ACM means asbestos containing materials (ACM) containing a bonding compound reinforced with asbestos fibers.
- 4. Refer to the on-site Building Management Plan (BMP) prior to carrying out any work to determine the type and location of any ACM (eg. asbestos-cement sheeting, vinyl tiles) that may be present. If the on-site Building Management Plan is not available then contact the Regional Safety/Asbestos Coordinator to examine the duplicate copy at the Regional Office to verify the presence/location of ACM.
- 5. If ACM is suspected (due to the age of the building and/or local knowledge) and there is no Building Management Plan and/or Asbestos Register on site, then an experienced and competent person is to undertake an inspection to identify the presence, type and location of any ACM that may be present prior to any work being carried out. If a competent person is also not available, then any suspect materials/products must be presumed to contain asbestos and is to be removed and disposed of as ACM in accordance with (company name) Standards and Legislative requirements.
- 6. The need for air monitoring is to be determined and documented by a competent person who is independent of the person responsible for the removal work, prior to any ACM related work being carried out.
- 7. All work involving ACM (removal, drilling, cutting of penetrations, scraping, repairing and/or clean-up etc.) is to be performed outside the normal operating hours of the facility/building and/or when the facility/building is unoccupied by arrangement with the owner/tenant.



# **Construction Signage**

The contractor is to ensure the placement of signs to prevent the access of unauthorized personnel to the site or hazardous work areas during construction and/or hazardous operations. Barricades/hoardings/fencing are to be of a standard construction that clearly defines and restricts all unauthorized personnel from entering the work area and exclusion zones and are to be erected in accordance with Statutory Authorities and manufacturers requirements. Access points must be kept always closed when personnel are not using them to enter and exit the work area.

# 1. SITE SAFETY SIGNS







# 2. CONSTRUCTION ENTRANCE SIGNS



# 3. CONSTRUCTION EXIT SIGNS





# 4. CONSTRUCTION AREA SIGNS



5. SIDEWALK SIGNS





# 6. CAUTION TAPE



The following references have been used in preparation of this report:

- 1-https://www.osha.gov/
- 2-https://www.ridemetro.org/

3- https://safetyrisk.net/wp-content/uploads/downloads/2010/06/whs\_construcsafe-plan\_all.pdf

# EXHIBIT "C"

# **NOTE: ALL SHEETS MUST BE REVIEWED**

DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES Herbert S. Saffir Permitting and Inspection Center 11805 SW 26th Street (Coral Way), • Miami, Florida 33175-2474 • (786) 315-2000

Job Address 8777 Collins Avenue Folio 14-2235-025-	Contractor No. CGC062660 Last four (4) digits of Qualifier No. 6086
Lot Block Subdivision PBpg Metes and bounds	Contractor Name Botam Construction Co, Inc Qualifier Name Gbolahan Austin Akinrin Address 1600 NW 3rd Avenue City MiamiState FL Zip 33130
[] New Construction on Vacant Land       [] Enclosure         [] Alteration Interior       [] Repair         [] Alteration Exterior       [] Demolish         [] Relocation of Structure       [] Shell Only         [] New Roof       [] Addition Attached         [] Recovery (Roof)       [] Re-Roof         [] Permit by Affidavit       [] Foundation Only	Current use of property <u>Vacant</u> Description of Work <u>Surfside Emergency</u> Shoring Sq. FtUnitsFloors Value of Work \$500,000
Image: Category 015     015     [] Chg. Contractor       [] Electrical     [] Re-Issue       [] Mechanical     [] Supplement       [] Plumbing     [] Reinspection       [] LPGX     [] Reinspection	Owner Miami Dade County - Police         Address 9105 NW 25 Street         City Doral       State FL         Phone         Last four (4) digits of         Owner's Social Security No.
Nome Austin Akinrin Address 1600 NW 3rd Aveue City Miami Stote FL Zip 33136 Phone (754) 245-0102	Name         Calc Engineering           Address         200 NW 89 Place, Unit 102           City         Doral         State           Phone         (305) 898-9995
Name	Name           Address           City

OWNER'S/PERMIT APPLICANT AFFIDAVIT I certify that all of the foregoing information is accurate. I certify that I am not a named violator with: unpaid civil penalties; unpaid administrative costs of hearing; unpaid County investigative, enforcement, testing, or monitoring costs; or unpaid liens, any or all of which are awed to MiamiDade County pursuant to the provisions of the Code of MiamiDade County, Flarida. WARNING O OWNER: YOUR DUBLE TO END A HOUSE OF COMPANY OF COMPANY OF COMPANY OF COMPANY.

IF YOU INTEND TO OBTAIN TRANCING, CONSULT WITH YOUR ATTORNEY OR "The issuance of the permit does not relieve the property owner from obtain authorizes work that is in violation of any association rule or regulation."	IINDER BEFORE RECORDING YOUR NOTICE OF ON MENCEMENT ng homeowner's association approval (if required) prigt to beginning and work and in no way
Signature of Owner or Owner's Agent	Signature of Qualifier
PRINT NAME	PRINT NAME GIRCLAREAD AUSTON ARIN RIN
STATE OF FLORIDA COUNTY OF MIAMI-DADE	STATE OF FLORIDA COUNTY OF NIAMI-DADE
Sworn to and subscribed before me this	Sworn to and subscribed before me this
day of, 20	doy of Adurist 2021
by	by Glost chief Alsm Bronn
Signature of Notary Public	Signature of Notary Jublig
Print Name	Print Name Protection Proventie Bryan
(SEAI)	(SEAL)
Personally known	Personally known The Bonded Through - Cynanotacy
or Produced Identification	or Produced Identification-Floreda - Notary Public



Department of Regulatory and Economic Resources

Environmental Resources Management 701 NW 1st Court, 6th Floor Miami, Florida 33136-3912 T 305-372-6567 F 305-372-6407

miamidade.gov

# **Class V Dewatering Permit Application Form**

For Departmental Use Only	
Date Received:	Application #:
Fee Received: \$	Tracking #:
<ul> <li>1. Checklist:         <ul> <li>Application Fee: Dependent upon duration of dew</li> <li>6 days or less \$5:</li> <li>7-30 days \$635.</li> <li>31-90 days \$980.</li> </ul> </li> <li>Note: After-the-Fact Permit applications will be charged departmental administrative enforcement costs.</li> <li>Complete description of dewatering operation ****</li> <li>Complete dewatering operation calculations***</li> <li>Site Plan (site plan shall include project be sedimentation tanks, turbidity barriers, discharge project be sedimentation tan</li></ul>	atering permit (all fees include a 7.5% RER surcharge): 20.00+\$39.00 = \$559.00* .00+\$47.63 = \$682.63** .00+\$73.50 = \$1053.50** d a penalty fee amounting to 100% of the original fee, plus oundaries, location of proposed dewatering activity, points, berms, monitoring points, etc.)*** EXTENDED, a new permit application will be required. calendar days prior to the time of permit expiration. ct or land surveyor, licensed in the State of Florida.
2. Project Information:         Project Name: Surfside Emergency Shoring         This application is for a(n):         ✓ New Permit         Location: 8777 Collins Avenue, Surfside, FL 33154         Section:	Folio #: 14-2235-025-         After the Fact Permit         imated completion date: 8/30/2021         Yes       No         Unknown
3. Applicant Information: This should be the applicant's information for contact purposes.         Name:       Austin Akinrin         Company:       Bofam Construction Co, Inc         Address:       1600 NW 3rd Avenue         Miami, FL       Zip Code: 33136         Phone #:       754-245-0102         Fax:       305-675-9269         Email:       Austin@bofaminc.com	4. Applicant's Authorized Permit Agent:         Agent is authorized to process the application, furnish supplemental information relating to the application and bind the applicant to all requirements of the application.         Name:
5. Contractor Information:         Name: Austin Akinrin         Licens:         Company: Bofam Construction Co, Inc         Address: 1600 NW 3rd Avenue, Miami, FL         Phone #: 754-245-0102         Fax#: 305-675-9269	zip Code: <u>33136</u> Email: <u>Austin@bofaminc.com</u>

#### 6. Performance Bond and/or Mitigation Fee: (to be assessed by Water Control Section)

- This permit may require a performance bond to guarantee that work is accomplished according to plan and that no
  impact to adjacent properties is generated as a result of the permitted dewatering activity.
- A mitigation fee may be required to compensate for any loss of or impact to natural resources due to the extent and duration of the dewatering activity.

Application is hereby made for a Miami-Dade County Class V permit to authorize the activities described herein. I agree to or affirm

### 7. APPLICANT AFFIRMATION:

<ul> <li>I possess the authority to authority</li> </ul>					
	thorize the proposed ac	ctivities at the su	bject property,	and	
<ul> <li>I am familiar with the information</li> </ul>	ation, date and plans co	ontained in this a	pplication, and	i	
<ul> <li>To the best of my knowledge</li> </ul>	e and belief, the informa	ation, data and p	lans submitted	are true, complete	te and accurate, and
<ul> <li>I will apprise the Department</li> </ul>	t of any changes to info	rmation provide	d in this applica	ation, and	
<ul> <li>I will provide any additional in project will comply with the a</li> </ul>	nformation, evidence or applicable State and Co	r data necessary unty water quali	to provide rea ty standards be	oth during constru	ce that the proposed oction and after the project
is completed, and					
<ul> <li>I am authorizing the permit a information relating to this are</li> </ul>	igent listed in Section 4	of this application	on to process t	the application, ful	rnish supplemental
Lagree to provide entry to the	a project site to inspect	applicant to all it	equirements of	tives of Miami Da	de County with proper
identification or documents a observation of permitted acti	as required by law, for the vities.	he purpose of pr	eliminary anal	ysis, verification, s	sampling, monitoring, and
A. IF APPLICANT IS AN INDIVID	DUAL				
Signature of Applicant	Print A	policant's Name			Date
Examples: Corporation, Partners	hip, Trust, LLC, LLP, et	tc.)	L PERSON		
Bofam Construction	Co, Inc	Corp			
Print Name of Applicant (Enter the comple	te name as registered)	Type (Corp, LL	C LLP, etc.)	State of Registra	ation/Incorporation
proof of such authority to the Depa documents, operating agreements, (ATTACHMENT "A").	rtment). Please Note: , or other applicable a	If additional si greements or l	gnatures are aws, you mus	required, pursua at attach addition	al signature pages
LEARWIN	AUSLIN ARI	INRIA	Treslue	ant	
Cignolyne of Arithenined Departments	Data & Authorized Deserves	station is bloom	Tist		
Signature of Authorized Representative	Print Authorized Represe	ntative's Name	Title	huo momboro lint	Date
Signature of Authorized Representative C. IF APPLICANT IS A JOINT V	Print Authorized Represe ENTURE Each party r	ntative's Name must sign below	Title (If more than t	two members, list	Date on attached page)
C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple	Print Authorized Represe ENTURE Each party r ete name as registered)	ntative's Name must sign below 	Title (If more than t C LLP, etc.)	two members, list	Date on attached page) ation/Incorporation
C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple	Print Authorized Represe ENTURE Each party r ete name as registered)	ntative's Name must sign below Type (Corp, LL Type (Corp, LL	Title (If more than t C LLP, etc.) C LLP, etc.)	State of Registre	Date On attached page) ation/Incorporation ation/Incorporation
Signature of Authorized Representative C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple Print Name of Applicant (Enter the comple	Print Authorized Represe ENTURE Each party r ete name as registered) ete name as registered)	Type (Corp, LL	Title (If more than t C LLP, etc.) C LLP, etc.)	State of Registre	Date On attached page) ation/Incorporation ation/Incorporation
Signature of Authorized Representative C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple Print Name of Applicant (Enter the comple Under the penalty of perjury, I certi	Print Authorized Represe ENTURE Each party r ete name as registered) ete name as registered) ify that I have the auth	Type (Corp, LL Type (Corp, LL	Title (If more than t C LLP, etc.) C LLP, etc.) is application	State of Registre State of Registre State of Registre	Date on attached page) ation/Incorporation ation/Incorporation
Signature of Authorized Representative C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple Print Name of Applicant (Enter the comple Under the penalty of perjury, I certi Applicant, and if so required to aut	Print Authorized Represe ENTURE Each party r ete name as registered) ete name as registered) ify that I have the auth thorize the issuance o	Type (Corp, LL Type (Corp, LL Type (Corp, LL	Title (If more than t C LLP, etc.) C LLP, etc.) is application half of the Ap	State of Registre State of Registre State of Registre State of Registre	Date on attached page) ation/Incorporation ation/Incorporation Applicant, to bind the , you must provide
C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple Print Name of Applicant (Enter the comple Under the penalty of perjury, I certi Applicant, and if so required to aut proof of such authority to the Depa	Print Authorized Represe ENTURE Each party r ete name as registered) ete name as registered) ify that I have the auth thorize the issuance of artment). Please Note: or other applicable as	Type (Corp, LL Type (Corp, LL Type (Corp, LL Type (Corp, LL Type (Corp, LL Type (Corp, LL Type (Corp, LL	Title (If more than t C LLP, etc.) C LLP, etc.) is application half of the Ap gnatures are	State of Registra State of Registra State of Registra State of Registra n on behalf of the plicant. (If asked required, pursua	Date on attached page) ation/Incorporation ation/Incorporation Applicant, to bind the , you must provide int to your governing at signarture proven
C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple Print Name of Applicant (Enter the comple Under the penalty of perjury, I certi Applicant, and if so required to aut proof of such authority to the Depa documents, operating agreements, (ATTACHMENT "A").	Print Authorized Represe ENTURE Each party r ete name as registered) ete name as registered) ify that I have the auth thorize the issuance o artment). Please Note: , or other applicable a	Type (Corp, LL Type (Corp, LL Type (Corp, LL Type (Corp, LL nority to sign th of a bond on be i f additional si ogreements or l	Title (If more than t C LLP, etc.) C LLP, etc.) is application half of the Ap gnatures are aws, you mus	State of Registra State of Registra State of Registra State of Registra non behalf of the plicant. (If asked required, pursua st attach addition	Date on attached page) ation/Incorporation ation/Incorporation Applicant, to bind the , you must provide int to your governing al signature pages
Signature of Authorized Representative C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple Print Name of Applicant (Enter the comple Under the penalty of perjury, I certi Applicant, and if so required to aut proof of such authority to the Depa documents, operating agreements, (ATTACHMENT "A").	Print Authorized Represe ENTURE Each party r ete name as registered) ete name as registered) ify that I have the auth thorize the issuance of artment). Please Note: , or other applicable a	Type (Corp, LL Type (Corp, LL Type (Corp, LL Type (Corp, LL ority to sign th of a bond on be i f additional si greements or I	Title (If more than t C LLP, etc.) C LLP, etc.) is application half of the Ap gnatures are aws, you mus	two members, list State of Registra State of Registra State of Registra State of Registra n on behalf of the plicant. (If asked required, pursua st attach addition	Date on attached page) ation/Incorporation ation/Incorporation Applicant, to bind the , you must provide int to your governing al signature pages
Signature of Authorized Representative C. IF APPLICANT IS A JOINT V Print Name of Applicant (Enter the comple Print Name of Applicant (Enter the comple Under the penalty of perjury, I certi Applicant, and if so required to aut proof of such authority to the Depa documents, operating agreements, (ATTACHMENT "A"). Signature of Authorized Representative	Print Authorized Represe ENTURE Each party r ete name as registered) ete name as registered) ify that I have the auth thorize the issuance o artment). Please Note: , or other applicable a	Type (Corp, LL Type (Corp, LL Type (Corp, LL Type (Corp, LL nority to sign th of a bond on be if additional si agreements or I	Title (If more than t C LLP, etc.) C LLP, etc.) is application half of the Ap gnatures are aws, you mus	State of Registra State of Registra State of Registra State of Registra n on behalf of the plicant. (If asked required, pursua st attach addition	Date On attached page) ation/Incorporation ation/Incorporation Applicant, to bind the , you must provide nt to your governing al signature pages Date Date